



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
A	Part-1				
1	Demolition of brick work & stone masonry including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (III) In cement mortar. Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC.	104.00	Cu.mt	0.00	0.00
2	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (I) R.C.C/ PCC work. Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC.	15.00	Cu.mt	0.00	0.00
3	Dismantling tiled or stone floors laid in mortar, any type of flooring including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC.	920.00	Sq.mt	0.00	0.00
4	Dismantling Wall tiles , laid in mortar , any type of flooring including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. Work complete including all type of tools, tackles,, safety measures , scaffolding etc complete as per instruction of Architect/EIC.	333.00	Sq.mt	0.00	0.00
5	Dismantling cement asbestos hard board ceiling, any type of ceiling, or all type of partition walls, wooden trellis work, acoustic ceiling including frames stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC.	70.00	Sq.mt	0.00	0.00
6	Dismantling of any type of doors, windows, ventilators etc.(wood of steel) shutters including chowkhats, architraves, holdfasts and other attachments etc complete and stacking them within all lead and lift. (i) Not exceeding 3 Sq.M in area	41.00	Each	0.00	0.00
7	Dismantling doors, windows, ventilators, grill etc.(wood of steel) shutters including chowkhats, architraves, holdfasts and other attachments etc complete and stacking them within all lead and lift. (II) Exceeding 3 Sq.M in area	5.00	Each	0.00	0.00
8	Dismantling fixed glazing including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC.	138.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
9	Removing any type of paint (dry or oil) including putty, primer and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC.	883.00	Sq.mt	0.00	0.00
10	Remove of existing Fabrication and steel structure including plates, rolled steel joists, channels, angles and all type of accessories etc. including stacking of the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	675.00	Kg	0.00	0.00
11	Dismantling of existing S.S. & Glass railing (Lift lobby area) including stacking the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	20.00	Rmt	0.00	0.00
12	Removal of existing Male toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank , Urinal , all type of cock , accessories , basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (Male Toilet)	2.00	Per toilet	0.00	0.00
13	Removal of existing Female toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank , all type of cock , accessories , basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (Female Toilet)	2.00	Per toilet	0.00	0.00
14	Removal of existing Existing attached toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank , all type of cock , accessories , basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (D Toilet)	1.00	Per toilet	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
15	RCC Core cut : Drilling with core cutting machine in RCC beams,slabs,floors etc.,for laying pipes and rendering the same in RCC 1:2:4 finishing the same to the satisfaction of the Architect/EIC.etc., complete, at all levels. The rate shall also include for providing EPOXY based water proofing compound for sealing the joints around the pipes upto any depth at all heights & levels. Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC. a) 100 mm dia	2.00	Nos	0.00	0.00
16	RCC Core Cut : b) 150mm dia.	22.00	Nos	0.00	0.00
17	RCC Core Cut : b) 200mm dia.	1.00	Nos	0.00	0.00
18	Providing & laying 230 mm thick Brick Masonry work using common burnt clay building bricks having crushing strength not less than 35 Kg/Sq. Cm. at all levels in cement mortar 1:5 (1 cement :5 fine sand) - including proper filling of all masonry joints, curing etc. complete. including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC. (II) Conventional brick work	11.00	Cu.mt	0.00	0.00
19	Providing and laying Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 Kg./Sq. Cm. in cement mortar 1:4 (1 cement : 4 coarse sand) in superstructure - at all floor levels including proper filling of all masonry joints, curing etc. complete.Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC.	100.00	Sq.mt	0.00	0.00
20	Providing 15 mm thick cement plaster in single coat on Rough (Similar)side of single or half brick walls for interior plastering all floor level and finished even and smooth in (ii) Cement mortar 1:4 (1-cement :4-sand).Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC. finishing with a floating coat of neat cement slurry.	540.00	Sq.mt	0.00	0.00
21	20mm thick sand faced cement plaster on walls upto height 10 metres above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1-cement : 3-sand) and 8mm thick finishing coat of C.M. 1:1 (1-cement : 1-sand) etc. complete.	35.00	Sq.mt	0.00	0.00
22	PCC (1:4:8) :Providing and laying cement concrete 1:4:8 (1- Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC.	6.00	Cu.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
23	Providing and laying sand bedding including watering ramming, consolidating and dressing etc. complete.	1.00	Cu.mt	0.00	0.00
24	Providing and laying ordinary cement concrete 1:2:4 (1-Cement 2-coarse sand: 4-graded stone aggregates 20 mm nominal size) for R.C.C including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement.	5.00	Cu.mt	0.00	0.00
25	Providing TMT Bar FE 500/500D reinforcement for R.C.C. work including bending, binding and placing in position, safety measures complete all floor level	450.00	Kg	0.00	0.00
26	<p>Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with I.S.I specification. Using Chlordene and Chiorpurfiles 20 EC. As Per 6131_paret-II Consentrarion Weight one percent is recommended i.e one litre 20 EC chemical emulsion with 19 liter give 1 % concentration inclusive of one litre chemical emulsion appication at the rate of 5 Litre chemical / Sqm of surface is recommended as per I.S.</p> <p>The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools , tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	6.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
27	<p>Terrace waterproofing : Providing and Applying of waterproofing treatment in terrace area as per below specification.</p> <p>Cleaning of existing Terrace +Surface & Crack filling: Carry out crack filling wherever required. Big cracks can be filled with Cement: Fine sand in ratio 1:3 or by using suitable exterior durable, polymer + cement-based crack filling compound of a reputed brand. Fill the hairline cracks up to 3 mm thickness with Asian Paints Smart Care Crack Seal by applying one coat of exterior primer and two coats of Crack Seal on the cracks. Intercut interval between these coats should be min. 10 – 12 hrs. Big joint cracks (up to 40 mm width) can be filled with Asian Paints Hybrid PU Sealant</p> <p>Damp Proof /Damp proof Ultra Application: -</p> <ul style="list-style-type: none"> ▪ Apply one coat of Asian paints SmartCare Damp proof With 25% dilution by water with the help of Asian paints Smart Care Roller 800 as a priming coat ▪ Allow it to dry for 4-6 hrs.in clear sun light. ▪ Apply second coat of Asian Paints Smart Care Damp Proof/Ultra Without Dilution with the help of Asian Paints Smart Care Exterior Roller 800. ▪ Apply third Coat of Asian paints SmartCare Damp Proof/Ultra Without dilution with the help of Asian paints Smart Care Exterior roller 800. ▪ Allow it to dry for 4-6 hrs.in clear sun light. <p>The whole work is to be executed through specialized agency with a guarantee of 10 years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools, tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instnction of EIC/Client/Architect.</p>	640.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
28	<p>Toilet Waterproofing : Providing and Applying of waterproofing treatment in toilet block as per below specification. The concrete surface must be brought into surface saturated dry condition (SSD). Providing & Applying 2 coats of high performance two component prepacked cementitious waterproofing, Dr. Fixit Pidifin 2K, with a mix ratio of (liquid: Powder), parts by wt. - 1:2 at the rate 0.55 - 0.58 Sq.mt / Kg for 2 coats to achieve the DFT of 1mm in a span of 4 - 6 hours with a roller / brush on the prepared concrete substrate. Over the splash zone / shower wall taking the coating up the full height and up to 1 meter height on vertical surface and on other walls and 0.3 metre on horizontal surface below threshold for complete bathroom waterproofing. All the coats to be applied in perpendicular direction to each other. Allow the coating to air cure for 3- 5 days before conducting water ponding test for 24 Hrs. The coating shall have Elongation at break > 50% as per ASTM D 412, Tensile strength > 1 N/mm² as per ASTM D 412, Adhesion strength: 0.80 N/mm² as per ASTM D 4541, crack bridging upto 1mm as per ASTM C 836, Water penetration (5 bar pressure) as per BS EN 12390.</p> <p>The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools , tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	30.00	Sq.mt	0.00	0.00
29	<p>Rising Dampness and Negative side waterproofing for internal walls: For rising dampness and encapsulation treatment of dampness on internal walls treatment to be done with Diasen -Watstop, a 3 component product having resistance to water ingress of 9.5 ATM for both Negative side and positive and should have excellent resistance to Salt. Diasen - Watstop to be applied in 2 coats at consumption rate of 1 kg/m². The application can be done by Brush or roller to give smooth and even finish good enough for putty/paint application. Work complete including all type of tools , tackles, scaffolding etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	70.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
30	Toilet Flooring : Providing and laying Lapato/Matt/Glossy/ Non Skid/Rustic finish /Sugar finish Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client , tile size (600 mm X 600 mm) including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction and approval by architect. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of tile is Rs. 40/Sqft	102.00	Sq.mt	0.00	0.00
31	Toilet Dado Work : Providing and laying Lapato/ Matt /Glossy/ Non skid,/Rustic finish/sugar finish Vitrified tiles in dado using minimum 10 mm thick tiles as per approved make list by architect /client (tile size 600 mm X1200mm) fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to IS 1443-1972, level, cured, undamaged, compact,rigid,resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification , and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes . Basic rate of tile is Rs. 45/Sq.ft	144.00	Sq.mt	0.00	0.00
32	Vitrified Flooring : tile size 800 x 1600 mm Providing and laying Lapato/ Glossy/ Matt/ Rustic/ Sugar/ Satin finish Vitrified tiles flooring using minimum 10 mm thick tiles as per approved make list or selected by Architect , tile size 800 x 1600 mm including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting of approved shade and colour in proper line and level as per detailed drawing / instruction and approval by architect.The rate shall be inclusive of protecting the flooring by plaster of Paris and plastic and/or bubble top sheets. Basic rate of tile is Rs. 70/Sqft.	472.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
33	Vitrified Flooring : tile size 800 x 1600 mm : Lift Lobby "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 70/Sqft.	98.00	Sq.mt	0.00	0.00
34	Providing and fixing Heat Resistant Terrace Tiles (300 mm x 300 mm x 20 mm) with SRI (solar refractive index) > 78, solar reflection > 0.70 and initial emittance > 0.75 on waterproof and sloped surface of terrace, laid on 20 mm thick cement sand mortar in the ratio of 1:4 (1 cement : 4 coarse sand) and grouting the joints with mix of white cement & marble powder in ratio of 1:1, including rubbing and polishing of the surface upto 3 cuts complete, including providing skirting upto 150 mm height along the parapet walls in the same manner.	540.00	Sq.mt	0.00	0.00
35	Providing and laying 25mm thick polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6-coarse sand) or L.M. 1.1.5 (1-Lime putty :1.5 - coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. All complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue.	292.00	Sq.mt	0.00	0.00
36	Providing and laying polished kota stone slab 25mm thick in risers of steps,skirting Dedo and pillars laid on 10mm thick cement mortar 1:3 (1- Cement : 3 coarse sand) and jointed with gray cement slury mixed with pigment to match the shade of slab including rubbing and polishing etc. All complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue.	12.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
37	Vitrified Skirting work: Providing and laying Lapato /Glossy finish vitrified tiles in skirting using minimum 10 mm thick vitrified tiles of approved make list or as selected by Architect of premium quality fixed in skirting on 10 mm thick Cement plaster 1:3 (1 cement : 3 coarse sand) and jointed with 6 mm thick-min. 75 mm height laticecrete grouting of approved shade and colour in proper line and level for average 125 mm height as per detailed drawing /instruction and approval by architect. Basic rate of tile is Rs. 70/Sqft.	21.00	Sq.mt	0.00	0.00
38	Lift cladding : 2400 x 1200 mm : BULL BERRY GREY "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 125/Sqft.	30.00	Sq.mt	0.00	0.00
39	Artificial Stone Flooring : Providing & laying approved quality 15 mm thick Artificial stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Artificial stone is Rs. 150/ Sqft.	4.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
40	Artificial Stone door frame (up to 250 mm width): Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness), in door frame etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue .Basic rate of Artificial stone is Rs. 150/ Sqft.	84.00	Rmt	0.00	0.00
41	Artificial Stone window sill (up to 250 mm width) : Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness), in window sill etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue .Basic rate of Artificial stone is Rs. 150/ Sqft.	58.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
42	Granite stone/ Artificial stone Pantry Platform: Providing & fixing two layers of Pantry Platform, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Granite stone, joined together with 1:4 Cement mortar beding / approved tile adhesive , to true plane & level or to slopes,or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 1'6", cutting stone as per required shape & size to fit sink & 3" to 9" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architec/EIC.sample mock shall be approved from Architect/EIC. Basic rate of stone is Rs.150/ Sqft.	7.00	Rmt	0.00	0.00
43	Artificial stone top Wash basin counter for toilet: Providing & fixing two layers of wash basin counter, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Artificail stone, joined together with 1:4 Cement mortar beding / approved tile adhesive , to true plane & level or to slopes,or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 1'6", cutting stone as per required shape & size to fit Wash basin & 3" to 9" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architec/EIC.sample mock shall be approved from Architect/EIC.Basic rate of Artificial stone is Rs.150/ Sqft.	7.00	Rmt	0.00	0.00
44	Double Leaf Flush Door finish with veneer & Glass view panel: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 4 mm thick veneer with matt finish monocoat polish as approved, wooden frame with matt finish monocoat polish with chamfering, 8 mm toughened Glass view panel size 2050 x 750 mm, Hardware fittings like concealed door closer or floor spring, Door handle ,lock , Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, , safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic Rate of teak veneer - 120/Sqft.	11.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
45	Single Leaf Flush Door finish with one side veneer & one side laminate: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with one side 4 mm thick veneer with matt finish monocoat polish and one side 1 mm thick Laminate as approved, wooden frame with polish, Hardware fittings like door closer, Door handle, Mortise lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Basic Rate of veneer - 120/Sqft. & Equivalent to VNR series laminate.	3.00	Sq.mt	0.00	0.00
46	Single Leaf Flush Door with glass view panel: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 1 mm thick VNR laminate s approved, 8mm toughened milky Glass view panel, door fixed on frame (excluding stone frame), Hardware fittings like concealed door closer or floor spring, Door handle, Mortise lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, bidding, safety measures, as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Equivalent to VNR series laminate. (Toilet Door)	39.00	Sq.mt	0.00	0.00
47	WPC shutter with laminate finish with glass view panel (Duct area): Providing and fixing in position 12 mm thick WPC shutter of approved make with VNR laminate finish as approved, shutter fixed with floor and above pivot of approved make, pivot cover plate, safety measures, lock & handle etc fixtures of approved make list with all necessary fittings etc. aluminium frame 25x30 Complete as per detailed drawings and specifications.	43.00	Sq.mt	0.00	0.00
48	Double Leaf Flush Door finish with paint & Glass view panel: Providing and fixing in position 32 mm thick BWP grade Double leaf flush doors of approved make, finished with both side enamel paint with matt finish as approved, wooden frame with matt finish monocoat polish with chamfering, 8 mm toughened Glass view panel size 450 x 750 mm, Hardware fittings like Door handle, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications.	15.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
49	Accoustic Door: Providing & fixing Single Leaf Flush Door 50 mm thick with both side veneer finish with Polish; Door frame shall be from Ply with -Veneer with matt finish monocoat polish, infill 25mm thick rockwool (48 kg/cumt density) with necessary vinyl gripper, necessary fittings. Hardware fittings like concealed door closer Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures etc shall be per approved make by Architect, bending, bidding, , safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic Rate for material only teak veneer - 120 /Sq.ft.	6.00	Sq.mt	0.00	0.00
50	Sliding window: Domal section : 27x65 mm series Supply & Fixing of Aluminium sliding window with powder coated as per by approved make & sample by architect/EIC. Frame section: 40 x 89 x 1.5 mm Shutter section : 27x 65 x 1.5 mm Mosquito shutter : 27 x 65 x 1.5 mm Glass : 5 mm thick clear reflective toughened glass of saint gobain or approved make list including EPDM Gasket, Woolen In Shutter, Multiple Lock, Anti Rattling Guide, Lock Guide, handle Antilifting, Shutter Corner Clit, Shutter wing Connector, Interlock EPDM Gasket, Interlock Guide, Anti Capillary Pad, Bush Bottom silicon all side & All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.	2.00	Sqm	0.00	0.00
	Total Amount				0.00
B	Part-2				
51	Toilet ventilator : Providing and fixing standard extruded of alluminium section of size 63 mm x 38.10 mm x 1.2 mm (jindal section: 2434 @ wt. 0.643 kg per mt with colour powder coated alluminium frame for ventilation with 5 mm thick frosted/milky glass with provision of exhust fan etc complete as per drawing.	2.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID


Sr. No.	Item Description	QTY	Unit	Rate	Amount
52	Applying two coats of Birla (white cement based) or Asian (acrylic lapy- putty) or equivalent & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.	2500.00	Sq.mt	0.00	0.00
53	Interior paint : Providing & laying of 3 (three) coats with Royale luxury Emulsion paint of Asian Paint or equivalent approved brand in shades and colour as directed on wall surfaces to give an even shade incl. scaffolding to at any height with all labour and material after thoroughly brushing the surface & making free from mortar droppings and other foreign matter including surface preparation etc.complete. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift, safety measures , performance warranty certificate etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer / paint application is to be done with the rollers. rate shall be including crack filling and levelling as per manufacturers specification.	2500.00	Sq.mt	0.00	0.00
54	Wall Punning : Providing and applying 12 mm thick (average) premixed formulated one coat gypsum lightweight plaster having additives and light weight aggregates as vermiculite/ perlite respectively conforming to IS: 2547 (Part - 1 & II) 1976, applied on hacked / uneven background such as bare brick/ block/ RCC work on walls & ceiling at all floors and locations, finished in smooth line and level etc. complete.	5.00	Sq.mt	0.00	0.00
55	EWC : Providing and fixing wash down water closet (European type W.C. pan with Jet) as per approved make of selection & shade with seat cover, P OR S Trap M.S. or G.I bracket , CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand) including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. Model Equivalent to CNS-WHT-959JSPP	4.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
56	Providing and fixing Consealed cistern tank with frame work & Flushing plate of as per approved make by architect. Model Equivalent to JCS-WHT-2400	4.00	Nos	0.00	0.00
57	Providing and fixing Metropole Flush valve dual flush of as per approved make of selection by architect . Model Equivalent to JCP-CHR-152415	1.00	Nos	0.00	0.00
58	Providing and fixing 12mm dia. Health faucet with 8 mm dia of as per approved make selected by Architect with flexible pipe of 1.mt. length and holding stands complete. Model Equivalent to ALD-CHR-573	4.00	Nos	0.00	0.00
59	Providing and fixing Counter top Wash Basin of as per approved make of selection including fittings and waste pipe etc. and fixing on wash basin counter by tile adhesive of approved make. Model Equivalent to JDS-WHT-25909	4.00	Nos	0.00	0.00
60	Providing and fixing 15mm dia Basin spout of as per approved make of selection. Model Equivalent to FLR-CHR-5441NK (Wall Mounted)	4.00	Nos	0.00	0.00
61	Providing and fixing 15mm dia two way Bib cock of as per approved make of selection. Model Equivalent to FLR-CHR-5041N	4.00	Nos	0.00	0.00
62	Providing and fixing chromium plated Bottle Trap of as per approved make of selection with necessary coupling of approved make for wash basin & sink. Model Equivalent to ALD-CHR-769L	8.00	Nos	0.00	0.00
63	Urinal : Providing and fixing Urinal with Pressmatic Flush Valve Round of as per approved make of selection including connecting the urinal with waste pipe and all works related to this item etc complete. Model Equivalent to URS-WHT-132530 + PRS-CHR-073	2.00	Nos	0.00	0.00
64	Providing and fixing in position Soap Dispenser of as per approved make of selection with soap container. Model Equivalent to ACN-CHR-1135N	4.00	Nos	0.00	0.00
65	Providing and fixing Toilet papers holder of as per approved make of selection or as directed by EIC. Model Equivalent to ACN1153N	4.00	Nos	0.00	0.00
66	Providing and fixing Towel rack of as per approved make of selection or as directed by EIC. Jaquar ACN-1121N	6.00	Nos	0.00	0.00
67	Handrayer : Providing and fixing in position of Handdrayer of as per approved make list. Work completed as per the instruction of EIC. Model Equivalent to HDR-SAP-M99ACS	4.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
68	Providing and fixing 15mm dia. Angular Stop Cock of as per approved make of selection. Model equivalent to FLR5053N	10.00	Nos	0.00	0.00
69	Providing and fixing 15mm dia. Sink Cock of as per approved make of selection. Model equivalent to: FLR-5347N	2.00	Nos	0.00	0.00
70	Providing and fixing Kitchen sink as per approved make including all fitting material including Fixing of with necessary plumbing work as per detail drawing and plumbing work .Material approved by architect/EIC. Nirali : Grace Plain-510MM X 432MM	2.00	Nos	0.00	0.00
71	Dustbin : Providing and placing in position S.S. Solid Pedal Bin with inner removable container of as per approved make and as selected by the Architect. Size: 10" X 15"	25.00	Nos	0.00	0.00
72	Providing and fixing 6 mm thick mirror of Saint Gobain/ Modiguard / Asahi as per approved make shall be fixed with profile frame section (copper/brass/silver/gray/black etc.). Provision shall be made for conceal led light work as per detailed drawing / instruction of architect complete. Rate shall be inclusive of frosting work as per detail drawing.	7.00	Sq.mt	0.00	0.00
73	Toilet Cubical : @1000(W) X 1500(D) x 2050(H) mm Supply & Installation of Toilet Cubicles as per as per Architect selection & approved make. 12 mm Compact Grade 1.5 mm thick laminate Board of the approved shade by Architect . Accessories for cubicles.1. Aluminum "U" Section with SS Exterior grade Finish.2. Aluminum "H" Section with SS Exterior grade Finish.3. Aluminum Top Rail with SS Exterior grade Finish.4. SS Coat Hook (SS 316)5. SS Privacy Thumb Turn (SS 316)6. SS Door Knob (SS 316)7. SS Hinges (SS 316)8. SS Adjustable Leg (SS 316)With Rubber lining and Screw Etc. Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.	2.00	Nos	0.00	0.00
74	JC shutter: Supply & Installation of Cubicles with shutter as per as per Architect selection & approved make. 12 mm Compact Grade 1.5 mm thick laminate Board of the approved shade by Architect . Accessories for cubicles.1. Aluminum "U" Section with SS Exterior grade Finish.2. Aluminum "H" Section with SS Exterior grade Finish.3. Aluminum Top Rail with SS Exterior grade Finish.4. SS Coat Hook (SS 316)5. SS Privacy Thumb Turn (SS 316)6. SS Door Knob (SS 316)7. SS Hinges (SS 316)8. SS Adjustable Leg (SS 316)With Rubber lining and Screw Etc. Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
75	Handicap toilet accessories: Providing and fixing Handicap toilet as per approved make , like one hinged rail , 4 nos of grab rail , including all type of fixtures , fittings,etc complete as per instruction of Architect/EIC. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC.	1.00	Pair	0.00	0.00
76	Providing and fixing S.S. Nahni trap for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with SS/ C.I scread down or hinged grating including the cost of cutting and making good the walls.	7.00	Nos	0.00	0.00
77	Urinal Partition: Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick or required size as per drawing, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth.	2.00	Sq.mt	0.00	0.00
78	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [A] 15 mm.	12.00	Rmt	0.00	0.00
79	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [C] 25 mm.	70.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
80	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [D] 32 mm.	30.00	Rmt	0.00	0.00
81	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [E] 40 mm.	40.00	Rmt	0.00	0.00
82	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [F] 50 mm.	25.00	Rmt	0.00	0.00
83	Providing laying and jointing in true line and level 50mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be cancelled as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	5.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
84	Providing, laying and jointing in true line and level 75 diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 75 mm diametre heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	110.00	Rmt	0.00	0.00
85	Providing, laying and jointing in true line and level 110 diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diametre x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	95.00	Rmt	0.00	0.00
86	Providing, laying and jointing in true line and level 160mm diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 75 mm diametre heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	10.00	Rmt	0.00	0.00
87	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low density, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(F) 75mm	60.00	Rmt	0.00	0.00
88	Providing and fixing gun metal gate valve with C. I. wheel of approved quality (screwed end) 40 mm nominal bore	2.00	Nos	0.00	0.00
89	Providing and fixing gun metal gate valve with C. I. wheel of approved quality (screwed end) 32 mm nominal bore	3.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
90	Fabricated work: Providing Fabrication & erection of steel structure as per drawings including materials, consisting of plates, rolled steel joists, channels, angles, chequered plates etc and also rectangular / square hollow steel sections, insert plates in RCC/Brickwork, anchor bolts for steel structure, sleeve pipes, anchor nuts, washers etc, straightening of raw steel if required, fabrication of steel structures with primer and minimum two coats of anti corrosive paint including preparation of supplementary sketches and detailed bill of materials supply of bolts, nuts, washers, shims, packs, putty. gas, welding electrodes and all other consumables, as required and carrying out surface preparation all complete. The scope includes loading, transportation ,unloading and delivery and erection site of all fabricated structures,, alignment and welding of all structures true to line, level, plumb and dimension, including rectification if any, splicing, site assembly all as per technical specifications and drawings, ,all complete.Contacto shall provide stability certificate for the fabrication structure. Rate inclusive of shop drawing.	1272.00	KG	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
91	<p>ACP Clading: Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including: (a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium item.s The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places. (For lift area cladding)</p>	8.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
92	Providing and fixing PUF Insulated continuous sandwich panels for roofs/walls of total thickness not less than 50 mm and width 1.0 m made out from continue line method on automatic plant.Panel shall have 0.5 mm thick pre coated GI sheet on both side of Polyurethane Foam confirming to IS 12436:1988.The Precoated sheet shall be of minimum 240 mpa steel grade confirming to IS 14246:1995 and shall have zinc coating of minimum 120 gsm as per IS:277:1992 , 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 micron.The PPGI Sheet shall have plastic protective guard film of minimum 25 microns to avoid scratches during trasportation.The panels shall be vertically joined together by tongue and groove joints. The PU Foam shall be selfextinguishing, fire retardant type having minimum density of 40 Kg/Cu.mt.(+ , - 2 Kgs) including 0.25 mm thick craft paper edging on both edges. The panels shall be fixed to the steel frame structure with minimum 5mm thick self tapping GI screws of required length and nos. with minimum spacing of 300 mm c/c. Including cost of all type of tools, tackles, scaffolding, all labour, materials, transportation, Finishing, accessories, silicon sealent if required,. Work complete for at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the Detailed specification, shop drawing, approved sample, instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Roof area shall be measured for payment.	138.00	Sq.mt	0.00	0.00
93	Providing and fixing 150mm wide 450mm over all semicircular plain G.I.sheet class- 3 gutter with Iron brackets 40mm x 3mm size Bolts, Nuts, washers etc. including making necessary connection with rain water pipes. (i) 0.80 mm thick Sheet. Including cost of all type of tools, tackles, scaffolding, all labour, materials, transportation, Finishing, accessories, silicon sealent if required,. Work complete for at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the Detailed specification, shop drawing, approved sample, instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	14.00	Sq.mt	0.00	0.00
94	Providing cement vata (10cm. x 10 cm. size) quarter round in cement mortar 1:1 including neat cement finishing, watering etc. complete.	195.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
95	Removing/chipping and cleaning of existing concrete carefully by low impact high frequency hammer without damaging the existing concrete or by control sand blasting including cleaning the surface by air jet etc. complete as per direction and satisfaction of Engineer-in-charge (for payment area of R.C.C member before chipping/ removing loose concrete will be measured).For any thickness of RCC members. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	5.00	Sq.mt	0.00	0.00
96	Applying two coats of alkaline rust converting primer of approved quality and make conforming to ASTM-B-117 (Cleaning existing reinforcement with wire/rotary wire brush, making the surfaces free from loose material, dirt etc. complete) on the rebars, including cleaning the reinforcement wire brushing to remove loose rust spalls, As per the recommendation of manufacturer complete as per direction of Engineer-in-charge. for Payment exposed length of reinforcement will be measured (Alkaline rust converting primer - REEBAKLENS RR of FOSROC / Sika Rustoff 100 of Sika / BASF/ Pidilite/ Krishna Conchem).Bars upto 12 mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	20.00	Rmt	0.00	0.00
97	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	10.00	Rmt	0.00	0.00
98	Providing and laying anticorrosive Treatment of Reinforcement by any approved make rebar corrosion protection system to existing reinforcement (The application shall be by brush). Process is to be complete as per the recommendation of manufacturer and direction of Engineer-in-charge. for payment exposed length of reinforcement will be measured. (Product - NITAZINC PRIMER of FOSROC /Friazinc® R of Sika/ MasterEmaco P 130 of BASF or equivalent of pidilite & Krishna Conchem).Bars upto 12mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	20.00	Rmt	0.00	0.00
99	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	5.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
100	Making 'V' groove of 5 mm wide and 5mm deep over crack line by electrically operated angle grinder with diamond concrete saw blade and cleaning it by air blower as directed by Engineer-in-charge Sealing of exposed 'V' groove of 5mm deep and 5mm wide with solvent-free, moisture tolerant, thixotropic, two part structural adhesive and epoxy repair mortar cum surface levelling mortar the compressive strength of the epoxy repair mortar shall be ≥ 60 N/mm ² (14 Days) and Bond strength ≥ 10 N/mm ² (7 Days). (Product -NITOMORTAR S OF FOSROC/ Sikadur®- 31 of Sika/ MasterBrace 2200 BASF or equivalent of Pidilite or Krishna Conchem). Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	20.00	Rmt	0.00	0.00
Total Amount					0.00
C	Part-3				
101	Driling and fixing NRV nozzles in RC members, including (fixing material : Renderoc Plug of Fosroc / Sikadur-31 of Sika/ MasterBrace 2200 of BASF or equivalent of Pidilite & Krishna Conchem). Drilling Holes: Drilling 12mm dia, 50 to 75 mm deep holes in structural members of the intervals of 350 mm in staggered manner or as directed by the consultants in RC structural elements. Cleaning of holes: Clean the holes by air blower prior to fixing nozzles. Cuttting of Nozzles: Cut the nozzles by chisel after completion of grouting without damaging structural elements: all type of structure Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	2.00	Each	0.00	0.00
102	Supply and apply a polymer modified cementious boand coat. Ratio polymer : water : cement (1 Polymer: 4 Water: 6 Cement) by weight. Apply the patching mortar when the bond coat is tacky (Nito Bond SBR Latex of Fosroc/ Sika® latex of Sika/ MasterEmaco SBR2 of BASF or equivalent of Pidilite or Krishna Conchem) Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	10.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
103	<p>Injecting/Grouting shrinkage free low viscosity epoxy resin grout in structural cracks, wherever required by pressure and using mechnaized injector gun with accessories till nozzles refused to accept the grout. Epoxy grout material should be conforming to ASTM-881-87 type I, grade I, class B & C and compressive strength of the material shall be \geq 55 Mpa, (7 Days), Tensile strength \geq 20 Mpa (14 Days) & Bond strength 10 Mpa (14 Days). (Low Viscous epoxy grout : conbextra EP10 of Fosroc/ Sikadur[®]-52 of Sika/ MasterInject 1315 of BASF or equivalent of Pidilite & Krishna Conchem).Mixing of material : Mixing material components in required quantities as per manufacture's instruction. Grouting : Fill the grouting gun with low viscosity epoxy resin. Maintain desired pressure in the gun by air compressor: maintain the required pressure at exit. Grout the material through prefixed nozzles in structural elements till its refusal, seal the nozzles with epoxy putty after the refusal, monitor leakages through other nozzles while grouting and seal them as per the requirement, repeat the process for all the nozzles. complete the operation within pot life of the material.Cleaning the gun and accessories: Clean the gun and accessories (valves, pipes and other fixture) with thinner after the operation to avoid jamming of the gun.</p> <p>Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	1.00	Kg	0.00	0.00
104	<p>CABLE RAILING : Providing & fixings SS cable with tensioners with required all accessories tool tackles etc with approved by architect at all height SS cable Style Left Hand Lay Cable Size3/16"Alloy Type 316, Work complete as per the approved sample & instruction of EIC. Work complete including all type of material, fittings , fixtures, (three row cable) fixed on the solid wall/RCC through brackets & anchor fasteners, Railing height to be taken at 1050mm from floor level, Finish, safety measures , loading , unloading , transpiration, all leads ,accessories, sample mockup, all floor , all levels, all heights , necessary frame work,Scaffolding etc complete as per detailed drawings ,specifications & instruction of Client/EIC.</p>	8.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
105	<p>Providing and fixing knock down handrail system comprising 50mm dia. Stainless steel pipe handrail (SS 316 - Matt Finish) mounted on the solid wall/RCC through brackets & anchor fasteners which will be placed at maximum 1200mm c/c distance and as per site requirement. Wall thickness of all Pipes shall be taken as 1.5mm along with all visible components developed in High Grade S.S. and whenever required, joints to be filled with bushings for extra strength. Wall Handrail height to be taken at 1000mm from floor level .Rates should be inclusive of welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the side of waist slab/wall with suitable arrangement as per approval of Engineer / Architect.Work shall complete includes all type of tools,tackles, all level & Height, labour, safety measures , mock sample etc complete as per the detailed drawing and instruction of EIC. Note :Handrail Lenght will be measured from Starting to End Location</p>	8.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
106	<p>Glass Railing : Providing and fixing of Alluminium (6063) glass balcony railing with powder coated as per approved shade by Architect/ Client. (Remson or equivalent make as per approved by Architect/client) System : Signature Line Continue Profile System Dimension : 75mm x 125mm , Hand Rail : Reactangle Handrail Hadrail Dimension : 60mm x 40mm Glass Specification : 10mm Clear Toughened + 1.52mm Sentey Film (Kuraray Make) + 10mm Clear Touhenend Railin Height : 1205mm , Custmised Wall Conceal Aluminium Make With 10mm x 120mm Hilti HRD Fastner.Hilti Chemical Fastner 10 x 40 with SS threaded Rod for Bottom Profile,EPDm Gasket As Per Glass size Work complete including all type of material, fittings , fixtures, Finish, loading , unloading , safety measures , transportation, all leads ,accessories, groove, PVC edge banding, adhesive ,tape, headless nails, sample mockup, all floor , all levels, all heights etc complete as per detailed drawings ,specifications & instruction of Client/EIC. Aluminium Powder coating-50 microns Powder coating 15 years warranty.only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client.</p>	18.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
107	<p>Gypsum 30min Fire Resistance ceiling: M/F Suspended 30min Fire Resistance ceiling includes Gypserra™ Perimeter Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS27)} is fixed along the perimeter of existing wall/ partition with the help of HILTI HPS - 1 (6x40) impact anchor, at 600mm centres. Gypserra™ Ceiling Angle {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is suspended by fixing it to the Gyproc® soffit cleat {GI(IS513)YS-260Mpa,Finish-Galvanised 150GSM(IS277) }. Soffit Cleat and Gyproc® Rawl Plug- Ø8x45mm {Material-IS 513 CR2 grade, Zinc coating (7 to 8 microns) pull out load- 6.8kN for M30 concrete grade} creating 1220mm x 1220mm grid. Gypserra™ Intermediate channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277) } is fixed to the Gypserra™ Ceiling Angle with M6 x 12mm Hex Bolt & Hex Nut arrangement {Material-As per EN 10083 Finish – Zinc Plating} or with 2 Nos of Ø4.2x13 Gyproc® metal to metal screw {Material-Carbon steel EN-ISO 7049/50 Finish-Zinc Coating Thickness- 4.14micron.} The Gypserra™ Ceiling Section {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is then fixed to the Gypserra™ Intermediate Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} with the help of Gyproc® Connecting Clip {Material-High carbon spring steel wire(BS970Gr.En42)-46-48HRC,Finish- Zinc plating 4-6 micron} and in direction perpendicular to the Intermediate channel at 457mm c/c. Use 50mm thick rockwool above ceiling for fire insulation, then Single layer of 15mm tapered edge Gyproc Firestop Board as per (EN 520: 2004, Type F) is then screw fixed to ceiling section with 25mm drywall screws {Material-Carbon steel EN-ISO 7049/50,Finish-Case hardened Grey Phosphating} at 230mm centres on ceiling section & 150mm at periphery of ceiling. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Easy-fill 90 Jointing compound (Conforms to ASTM C475), Gyproc® Joint Paper tape. Serrated section has effective thickness of 2T (2xdepth), better load carrying capacity.</p> <p>The item includes providing and fixing trap door of size 600 X 1200 mm as per approved sample of Ceiling panels comprise of a powder-coated beaded steel frame with gypsum / plywood board door. Each panel features a push- latch closing mechanism with door retaining safety cable & hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, , safety measures necessart framing work if required etc. complete work. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price.</p>	882.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
108	<p>Grid Ceiling: Providing & Fixing of Eco- Friendly Light weight Calcium Silicate Ceiling .Providing and Fixing False ceiling at all heights 100% Eco Friendly , Non Cementitious light weight calcium silicate false ceiling tiles having having 15 mm thick integral densified edges (for extra Strength) reinforced with Eco-friendly fibres and natural filler with a eco-friendly recycled content of more than 50% (For Green Building Leed Accreditation) . False ceiling tiles of Size 595x595 mm of approved texture, design and patterns Viz Spintone/ Cosmos/ Spectra /Globe/Hexa/Quadra having NRC (Noise Reduction coefficient) 0.50 to 0.75 (for semi perforated and fully perforated range of tiles), Light reflectance of 85% (minimum) . Non-combustible as per BS: 476 (part-4), fire performance as per BS: 476 (part 6 &7 (High Fire resistivity for very high fire safety), humidity resistance of 100% RH (Suitable for any weather conditions) , Thermal conductivity of 0.050 W/m²KC to 0.050 W/m²KC as per IS 3346/1980 (High Thermal Insulation). 100% Antifungal , Antibacterial, Anti termite.The ceiling Tiles should be free from Chemicals, asbestos having Zero VOC Property for better indoor Air quality The tiles shall have average body density of 370 kg/m³ as per ECBC code 2007 and average edge density of 450 Kg/m³. The tile shall be primer coated on both sides and the fair surface shall be having a factory finish in two coats of white dispersion type solvent free paint.The framework shall be suspended from ceiling by slotted cleats of size 25X35X1.6mm fixed to ceiling with 12.5mm dia and 50mm long dash fasteners, 4mm G.I. adjustable rods with galvanized steel level clips of size 85X30X0.8mm, spaced at 1200mm centre to centre The tile shall be laid on 24x38mm wide T section flanges colour white having rotary stitching on all T sections, i.e., the main runner, 1200 mm & 600 mm cross tees with a web height of 38mm & load carrying capacity of 11-13kgs/Sqm. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge/Manufacturers Specification. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price., safety measures , No separate charges for cutting / providing opening will be paid. Trap doors with necessary ply frame workto be provided as required at no extra cost. Work complete as per the detailed drawing and instruction of Architect/EIC.</p>	160.00	Sqmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
109	<p>Grid Ceiling of Advantage™ E : Providing and fixing tiled false ceiling of size 600x600 mm in true horizontal level suspended on interlocking Gyproc® Bolt-slot grids. It consists of main T runner of size (35x15x0.3x3000)mm, Gyproc cross T runner of size (35x15x0.3x1200)mm, Gyproc® secondary cross T runner of size (35x15x0.3x600)mm, (0.5x600/1200x150/300)mm of plain metal planks. Gyproc®Ceiling fastener with bracket is fixed to soffit , creating (1200 x 600/1200)mm grid. Gyproc® Main T runners are then suspended at 1200/600mm c/c from ceiling using 4mm zinc electroplated butterfly level clips of size (85x30x0.8)mm spaced at maximum 1200mm center to center along main T runner and not more than 150mm from spliced joints. The last hanger at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200 mm cross T is interlocked between the main T at 600mm center to center to form a grid of 1200x600mm and then Gyproc® 600 mm secondary cross T is then interlocked at middle of the (1200x600)mm grid to form grids of (600x600)mm. Cross T at the ends having length more than 600mm are to be supported independently. Finally, Ecophon Advantage E tiles of size (595x595)mm and overall thickness 15mm, NRC≥0.95 and Metal Plank of size (1200x150)mm are placed in the grid.</p> <p>Technical row is created by running two parallel Main Ts with the desired distance of 150/300 mm between the Main Ts. For continous light Saint-Gobain Gyproc Adjustable Grid spacer to be used instead of 150 mm cross T. Saint-Gobain Ecophon Advantage™ E with tegular edge and 15 mm thickness, visible surface of each tile is 7 mm below the grid, visible surface is a batch painted glass tissue in white, back of the tile covered with glass tissue. • Size 600x600x15mm. • Acoustics-Sound absorption (Alpha W) - 1 at 200 mm o.d.s as per EN ISO 354 • Acoustics-Sound absorption Class - Class A at 200 mm o.d.s as per EN ISO 11654. • NRC - 0.95 NRC as per ASTM C 423. • Fire Safety - Tested and classified as non-combustible according to EN ISO 1182 with reaction to fire classification class A2 s1 d0 according to EN 13501-1 – European Standard. • Flexural tensile strength - Class C/3N • Indoor Air quality - Complying with the French regulation on VOC emissions, A level. Certified by the Finnish Building Information Group (RTS) with the M1 label. Certified by Eurofins Indoor Air comfort® . • Product Certified under GRIHA council of India for Green Ratings, IGBC Green Pro certified, Comply with the REACH regulation of the European chemical Agency, certified by the EUCEB which confirms that mineral wool is produced in conformity with the Note Q of EC No 1272/2008 and therefore classification as a carcinogen does not apply. • Environmental Footprint - Environmental Product declaration (EPD) acc to international ISO 14025 & EN 15804 series of standards. • Circularity - Minimum post-consumer recycled content 47%, Fully recyclable• Humidity Resistance -Class C, relative humidity 95% and 30°C, according to EN 13964:2014 • Light Reflectance - 83% light reflectance.Cleanability- Weekly dusting and vacuum cleaning. • Accessibility - The tiles are easily demountable</p> <p>CE Marking - Ecophon ceiling systems are CE marked according to the European harmonized standard EN13964:2014. CE marked construction products are covered by a Declaration of Performance (DOP) which enables customers and users to easily compare performance of products available on the European market. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, beads and also provide support/ template where ever required.The rate shall be in sq.mt for all floors and at all heights including all costs .</p>	40.00	Sqmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
110	Wooden ceiling finish with Veneer: Providing and fixing IS 710 12 mm thick Marine plywood ceiling finish with 4 mm thick veneer as per drawing, instruction, sample approved & complete with Aluminium anodised section size 50x50x1.5 mm & 25x50x1.5 mm / GI frame work. the frame work fixed as per drawing @ 600 mm c/c. finish with 4 mm thick Veneer with matt finish monocoat polish. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, CNC engraving , beads and also provide support/template where ever required. The rate shall be in sq.mt for all floors and at all heights including all costs. (or a sample mock of 5 Sqm minimum of the frame work and ceiling) shall be approved from Architect. 5mm Groove shall be provided at the junction of the ceiling & the wall. (considering all levels with require all Framing work and fitting from RCC slab to ceiling level). Basic rate of teak Veneer 120/Sqft	6.00	Sq.mt	0.00	0.00
111	Wooden ceiling finish with Laminate : " -----Do-----" as per above specification for complete work. Only finish with laminate instead of veneer. Equivalent to VNR series laminate.	5.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
112	<p>Accoustic ceiling : Providing and fixing with 9mm thick acoustical panel with using framing and then fixing 12.5mm perforated board with the help of screw and using rock wool of 50kg density and 50MM thick between framing and perforated sheet then Fixing Ecotone make Marco polyester fiber acoustic paneling with the specification of 9MM thick having density of 1.90kg/m2 with NRC value of 0.80 surface matt finish which is fixed with solution SR505 as required. The panel should have euro class BASTME84-13 fire rating.</p> <p>The color shade of Panel as approved by Architect.</p> <p>The work shall be done as per specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor/Supplier shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Work complete as per the Detailed Drawing, & instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required. The rate shall be in sq.mt for all floors and at all heights including all costs material and fittings, scaffolding. make list - Senses akustik , woven image , fliz felt.</p>	28.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
113	<p>Full Height Partition Gypsum Partition (60min. fire rating) : Providing & Fixing 110mm thick Gypwall Classic partition consist of GypSerra™ (“Patented in India (325062)”) Metal framework partition having maximum reachable height of 3700mm satisfying L/240 criterion at 200Pa,possessing fire rating of 60mins, tested in accordance to BS-476 Part 20 & 22 & sound insulation (Rw) of 53*dB, tested in accordance to ISO 10140-2/ASTM E90 & spectrum adaption term as per ISO 717-1, having U-value of 0.48W/m²K & Severe duty rating as per BS 5234 part 2. Partition comprises of double layer, tapered edge Gypsum Board, certified GreenPro by CII & strategic location of manufacturing plants results in lower carbon emissions. \$ Partition includes Outer layer of 15mm thick Gyproc®Fireline conforming to IS 2095 PART1 :2011 / EN520:2004 - TYPE-F, ASTM C1396-TYPE X, having flexural strength – {Longitudinal > 650N & transverse > 250N} & Outer Layer 15mm thick GypSerra™ Plain ISI marked,conforming to IS 2095 Part 1:2011, having flexural strength – {Longitudinal > 650N & transverse > 220N} on either side of the framing. GypSerra™ Metal frame work, designed in compliance with BS EN 14195 & manufactured using CR1 Grade Steel as per IS 513, having yield stress of 300MPa & tensile strength of 340MPa with surface finish of AZ150 as per IS 15961/AS 1397 & tested for 500hrs of salt spray test as per ASTM B117, includes 48x34x36x0.5mm GypSerra™ C-Stud with lip of 6.5mm and H-cutout on web enabling the services to pass, having moment of inertia 26627mm⁴ about major axis, positioned at 610mm c/c in 50x32x32x0.5mm GypSerra™ Floor Channel & 50x32x32x0.5mm GypSerra™ Ceiling Channel with flanges bend at 5° acute angle. Floor & Ceiling Channel is anchored with Gyproc® Rawl plug Ø8x45mm having Pull Out strength of 6.8kN or Nail**, fixed at 600mm c/c in Center. 48x40x40x0.5mm GypSerra™ Noggin Channel to be placed between the studs, behind the horizontal board joint. Gyproc®Fireline Board strip is placed between Ceiling Channel and soffit when fire rating is more than 30mins.Inner & Outer layer of Gyproc® Boards to be Screw fixed with Gyproc®Drywall Screw of 25mm with 12nos per m² & 50mm with 24nos per m² at spacing of 600mm & 300mm respectively. 25mm Glasswool of density 32kg/m³ shall be placed in Metal framework with the help of holding Clip. Edges & joints to be finished with Gyproc® Pro-Fill JC conforming to ASTM C475 & Gyproc®Paper tape. Periphery & cut-outs of the partition to be treated with suitable Fire & Acoustic Sealant. All the performance test are carried out at NABL accredited/ government approved lab. For fire certification, the site contractor to involve the Saint-Gobain Gyproc technical team before the start of installation. Stagewise site photos are mandatory for fire certification. Vendor to submit MTC, material inspection report and/or performance certificate for the system.The junction of the partition with masonry & all penetration through the partition has to be treated with Hilti/Pyroplex fire and acoustic sealant. All other detailing and specifications to be followed as per approved drawing of Gyproc.Note: Applicator need 60min. fire rating certificates from Gyproc.Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required & For door frame fixing, storages, shelves, paneling etc extra Wooden members to be used shall be of CP teak wood only. Including skirting /MDF board/wooden skirting cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. including ply base for fixing of TV or Overhead storage wherever required, The rates are also inclusive of necessary scaffolding, tools, tackles,, safety measures , Internal partial support .The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. All exposed corner shall be covered with perforated angle as per manufacturer's specifications or as directed by EIC. Partition ht will be measured from finish floor to false ceiling level only. Work inclusive of above ceiling solid partition framework as per drawing. Contractor shall take care noise for transformation one Area to another area.</p>	154.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
114	<p>Wooden solid Partition finished with Both side VNR Laminate: Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work on both side finish with 1mm thick Laminate. The frame work shall be made from square hollow aluminium section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment . Both side finish with VNR Laminate. Glass shall be Lacquered glass as per selection by Architect / EIC. Rates shall also be inclusive of cost of making cut outs/ openings for MEP services & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. work complete including all type of material, fittings , fixtures, Finish, loading , unloading , safety measures , transportation, all leads , accessories, groove, PVC edge banding, adhesive ,tape, headless nails, sample mockup, all floor , all levels, all heights etc complete as per detailed drawings ,specifications & instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. work inclusive of above ceiling solid partition framework as per drawing. Contractor shall take care noise for transformation one Area to another area. Equivalent to VNR series laminate.</p>	96.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
115	<p>Thin Profile Glass Partition: Providing & Fixing of STL45 ie.Single glazed modular system consist of Aluminium section of 25*45*2.5 mm thick. All sections duly Powder coated/anodised with 6063-T6 grade and required accessories ie glass to glass aluminium I sections, T section & 90 degree sections & Glass packing to adjust the floor level. Ceiling profile, Floor profile and wall profile are 25 mm visible face and 45 mm wide with 10mm toughen glass as per approved make & insertion of Thermoplastic gasket to adhere the glass firm & airtight.The sound reduction Value is from 32 to 35 Db.With 6 mm Groove inbuilt in system to accomodate the carpet & the uneven surfaces.Work including horizontal thin profile member at lintel lvl. as per drawing.</p> <p>Accessories/Hardware: neutral cure glazed & metal silicon sealant of approved make on the periphery of the glass & wood etc.</p> <p>work inclusive of above ceiling solid partition framework as per drawing. Contractor shall take care noise for transformation one Area to another area.</p> <p>Partition ht will be measured from finish floor to false ceiling level only. The rate shall be in sq.mt for all floors and at all heights including all costs. Glass width size shall be as per suggestion by EIC.</p> <p>Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, safety measures, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	85.00	Sq.mt	0.00	0.00
116	<p>Frosted sparkling glass film (Colour film) : Providing and fixing frosted glass film of approved make Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs. MCS warranty of 3 (if exposed to direct sunlight) to 10yrs (indoors) must be endorsed by manufacturer. Rate shall be inclusive plotter cutting design as per Architect/Client suggestion. Contractor shall provide shop drawing for approval of Architect/Client.work complete incuding all type of tools, tackles, scaffolding etc complete as per suggestion of Architect/Client. If in case any application finishing will not as per satisfaction contractor shall remove all film at their cost. Contractor shall do a sample mock of 5 Sqm minimum of glass film), shall be approved from Architect/Client.</p>	52.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
117	<p>Alluminium Skirting : Providing and Fixing ofAluminium Skirting as per approved make having width of 75 MM X thickness of 2mm made out of 6063 Grade Aluminium alloy duly anodised as desired in the Ral Colour code decided by the architect having neat screw fixed arrangement with Rubber seal over it as per Manufacturers Specification. work complete as per the instruction of Architect. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads,all accessories as described in item description.</p>	200.00	Rmt	0.00	0.00
118	<p>Single Leaf Glass Door: Supply & Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 & KOPS DF 103 (45mm x 25mm) for Glass door frame Doorframe Dimension – 45mm x 25mm. Finish – SILVER finish / Powder coating as per approved sample by Architect 10mm thk. clear toughened Glass KUBIK Glass Hinge , HAFELE Open Door closer with saddle plate , KUBIK Mortise lock with handle , KUBIK Door stoper etc complete Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , necessary frame work,Scaffolding , safety measures etc complete as per detailed drawings ,specifications & instruction of Client/EIC.</p>	32.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
119	<p>Veneer panelling: Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work finish with 4mm thick Veneer & matt finish monocoat polish. The frame work shall be made from square hollow aluminium anodised section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment . Measurements for paneling work to be recorded upto finished false ceiling level only irrespective of aluminium frame work, which shall be provided from gr. level to RCC slab / beams soffit level. Rates shall also be inclusive of cost of making CNC/engraving /cut outs/ openings for electrical fixtures, tube lights /air-conditioners ,grills, diffusers etc & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. All curved surfaces, recesses, waffles shall be part of the paneling including openable shutter wherever required area and finished with the same material.Work complete including all type of material, fittings , fixtures, Finish, loading , unloading , transportation, all leads ,accessories, groove, adhesive ,tape, headless nails, sample mockup, all floor , all levels, all heights etc complete as per detailed drawings ,specifications & instruction of Client/EIC. only the clear elevation area of finished plywood wall paneling with Veneer shall be measured and paid. sample mock shall be approved from Architect/Client. Basic rate of veneer is 120/ Sq.ft</p>	90.00	Sq.mt	0.00	0.00
120	<p>Laminate Panelling : " -----Do -----" as per above item specification for complete work . using 1 mm thick laminate instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate. Equivalent to VNR series laminate.</p>	72.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
121	<p>Gypsum panelling: Gypsum panelling :The M/F wall lining includes 12.5mm Gyproc® Quattro Gypsum Board, screw fixed with drywall screws of 25mm at 300mm centers to one side of 45X18X0.5mm Gypliner ceiling channel (0.5mm thick having 18mm flange each made of GI Steel) placed at 600mm center to center in 195X29.5X0.9mm fixing bracket at 900mm c/c with 25X25X0.5mm Gypliner angle at bottom and top of the channel such a manner that joints staggered to avoid leakage through joints. Fixing strip of 75X0.5mm should be installed at horizontal joint of boarding. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Jointing compound and Joint Paper tape. 50mm Glasswool of density 20kg/m3 should be placed in metal frame.Necessary fabrication with anticorrosive paint work , scaffolding, anchor fasting , bolting HILTI or equivalent make with testing certified in scope of contractor)Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. Panelling item including openable shutter wherever required area and finish with the same material. Only the clear elevation area shall be measured and paid.</p>	20.00	Sq.mt	0.00	0.00
122	<p>Accoustic Panelling : Providing and fixing Accoustic Panel board 9 mm thick Artois /Aerolite/ Ecotech as per approved make & Sample by Architect/ Client. Supplying Marco Polyester Fiber acoustic wall paneling.Thickness:- 9 MM Density:- 200 kg/m3 , NRC: - 0.75 @ 125-4000 Hz Noise. Fire performance:- Class A , Accoustic board fixing on wall directly with SR 505 Adhesive or otherwise fix on 6 mm thick base ply & framing work . Work Inclusive of Cutting as per detailed drawing and instruction of Architect. Including surface preparation, Including cost of all type of tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.Only the clear elevation area shall be measured and paid.</p>	87.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
123	Cement Sheet panelling: Providing & fixing 8mm thick hilux or equivalent calcium silicate sheet fixed on frame work. The frame work shall be made from square hollow aluminium anodised section size of 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. (For Lift cladding)	22.00	Sq.mt	0.00	0.00
124	Extra labor rate for providing various sizes as per the detailed drawing CNC cutting / Engraving work for any type of material approved by EIC / Architect. The rate shall be for all floors, at all heights, all shapes including all costs.	5.00	Sq.mt	0.00	0.00
125	Soft Board : Providing and fixing on wall 12mm thick approved quality soft board with cotton cloth/fabric of approved make and shade on 12mm thick IS 710 ply 50 mm th approved Glass wool sheet with PVC grip , as approved sample and as directed by EIC. The work shall be measured & paid in Sqm. for all floors, all level and at all heights including all costs .Only the clear elevation area of the cloth/fabric shall be measured and paid. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC.Basic rate of cotton cloth /fabric for 54" wide shall be Rs. 200/Rmt.	3.00	Sq.mt	0.00	0.00
126	Ply palmet : Providing and fixing wooden pelmets of upto 200 mm x 300 mm L shape made of 19mm thick ply as per IS 710 and beading of 4mm thick and 25mm wide Ghana Teak wood for projection screen. Rate to be inclusive of lipping, cutting, wastages, necessary fixtures, nails, adhesives, necessary scaffolding, fixing at all heights and for all floors as per drawing and approved sample etc should also take load of all the all roller blinds.	100.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
127	<p>Roller Blinds : Providing and fixing blinds as per approved make as per suggested shade & spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar. Fabric : screen classic 3% to 5% Fabric value : 470 Gsm , Thickness : 0.60 to 0.70 mm Construction: 75 % PVC & 25 % Polyster Fabric to be as per approved sample. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC. All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the pelmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping.& mockup sample approved by the Architect/ EIC.</p>	103.00	Sq.mt	0.00	0.00
128	<p>Black out curtain: Providing and fixing Blackout curtain/blinds as per approved make as per suggested shade & spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar. Construction: 100 % Polyster Coating: Blackout 3 pass foam coating Thickness : 0.60 mm Fabric value: 390 Gsm , Fabric to be as per approved sample. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC.All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the pelmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping.& mockup sample approved by the Architect/ EIC.</p>	9.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
129	<p>Writable with magnetic glass board : Providing & fixing 04mm SGG Pristine Tan Glossy Finish writable & Magnetic CEP board on existing partition/wall as per approved sample by Architect/Client. work Including cost of all type of fittings , accessories , tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.Only the clear elevation area shall be measured and paid.</p>	30.00	Sq.mt	0.00	0.00
130	<p>GMD table unit : Table top : 2100 x 900 x 750mm, Side Unit - 1500 x 450 mm, Pedestal Unit-400x470X545. Providing and fixing table unit consist main table, side table ,back storage with pedestal unit with all necessary accessories keyboard, CPU stand ,cable manager, modesty panel etc with all required necessary accessories. All finishes laminate,powder coating /anodizing shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect.Contractors shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client All Table top : 50 mm thick postfoam top (reverse bull nose) with 1 mm thick VNR laminate finish as per approved make and sample by Architect/ Client. Verticle support: comprising from IS 303 BWR ply with both side finish with 1 mm thick VNR Laminate Wire management: Raceway :0.8 mm thick CRCA horizontal and vertical raceways with metal separator .one way or two way openable flip top box mounted on table top squeeze :A special flexible rubber component that allows easy and safe passage of wires. All the exposed edges are sealed with 2mm thick PVC Imported edge banding on sides and bottom. The top and drawer facia are sealed with 2mm thick PVC edge. The drawer unit consists of 1 box drawer and 1 file drawer. The drawer box is fitted with telescopic channel Hettich or Haffle make for free movement. The drawer unit is provided with central locking system, where in the drawer are locked with one key.SS 304 recessed handles are provided for easy opening and closing of drawer. The drawer unit is fitted on castors (optional) for easy mobility. PVC edge banding are imported from Rehau or Dolken of Germany. The complete furniture unit is factory assembled with knock down fittings.Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, monocoat polish, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing , mockup sample and instruction of Architect/Client. Equivalent to VNR Series Laminate.</p>	1.00	Unit	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
131	<p>Cabin table unit: Table top : 1500 x 750x750 mm ht, Side Unit : 1500x 450x750 mm ht, MDU-450x450x650mm, Providing and fixing table unit consist main table, side table with MDU unit with all necessary accessories keyboard, CPU stand ,cable manager, modesty panel etc. with all required necessary accessories. All finishes laminate, powder coating shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect. Contractor shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client</p> <p>All Table top : 35 mm thick post foam top edge finish as per selection and laminate as per selection suede /satin/VNR finish</p> <p>Flip open-Aluminium powder coated flip open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets</p> <p>Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN & electrical cables</p> <p>Vertical Legs and support : Made from metal as per selected design and powder coating finish</p> <p>Modesty panel: Made formed/Partial prelaminated edge finish PVC considered on the main spine and leg to leg modesty is considered</p> <p>MDU: Made up of with prelaminated MDF/particle board and all exposed edge finish with 2 mm th matching PVC edge banding. Hardware make hettich/haffle or equivalent. Providing 3 nos drawers with profile handle as per selection including locking arrangement</p> <p>CPU stand keyboard - as per selection with approved powder coated</p> <p>Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, finishing, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing , mock-up sample and instruction of Architect/Client. VNR Series Laminate.</p>	9.00	Unit	0.00	0.00
132	<p>Reception Desk: " -----Do-----"-as per above specification for complete work.</p> <p>Table top : 1200-1500 x 600 x 750 mm, Top thickness - 25 mm</p>	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
133	<p>Cabin Back side storage unit (750 H x 450 D) mm: Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect. Storage top : 35 mm thick post foam top edge finish as per selection and laminate as per selection suede /satin/VNR finish. Solid Shutter : 25 mm thick comprising from IS 303 BWR ply & finish with 1 mm thick VNR Laminate . Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate. Ledge/Niche comprising from IS 303 BWR ply finish with 1 mm thick Laminate , required lighting arrangement. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives , grooves , consumable hardware & required SS 304 grade hardware/accessories , Profile handle , Wooden frame, monocoat polish , pvc edge banding , of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. Contractor shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	7.00	Sqmt	0.00	0.00
134	<p>Console : Providing & fixing Console complete as per drawing/Ref Image. Approx size : 1500 x 400 x 600 mm made from up of 19 mm thick BWR grade ply & finished of Veneer with polish as per approved make and shade and solid wooden leg with matt finish monocoat polish as per drawing. Rate shall be inclusive of providing, fixing all necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Rod locks, Multipurpose lock, Rate shall be inclusive of internal shelves of 19mm thick IS 303 BWR ply and laminate , PVC edge beading . All external & internal exposed woodwork to be finished in PU semi gloss paint finish polish as per specified item's manufacturer's specifications. Rate shall inclusive of providing mock up sample for approval of architect.</p>	3.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
135	<p>Conference room table : 3800 x 1200 mm Providing and fixing as per detail shape and size table unit consist table with all required necessary accessories. Table size :3800 L x 1200B x 750H mm Top 50 mm thick comprising from 15-16 mm thick Artificial stone as per approved sample (reverse bull nose). Base & Vertical support comprising from ready made leg Metal finish as per approved sample by Architect. Ply box for cable runway comprising from IS 303 BWR ply with both side 4 mm thick Veneer finish with polish. Popbox: Flip open-Aluminium SS finish or approved finish open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN & electrical cables. Rate inclusive of providing and fixing as per requirement of socket and quantity Pop up tabletop electrical WIRE MANAGEMENT BOX SS finish. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/accessories, grooves pvc edge banding , etc of approved make for all floors, monocoat polish, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Basic Rate of Veneer is Rs.120/ Sqft. Basic rate of stone is 450 / Sq.ft .</p>	1.00	Nos	0.00	0.00
136	<p>Meeting table : @3500 x 1050 x 750 mm : " -----Do-----" as per above specification for complete work.</p>	1.00	Nos	0.00	0.00
137	<p>Meeting table : @1950 x 900 x 750 mm : " -----Do-----" as per above specification for complete work.</p>	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
138	<p>Workstation : L Shaped : Providing and fixing desk based L shaped workstation of size 1500-1600x600x1050 one side and other side 1500x600x1050 ht (Ht: 750 mm workstation + 450 mm Lacquared Glass including bracket) at below mentioned locations. Contractor shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client</p> <p>The table top-Table top to be made up of 25 mm thk prelaminated MDF/particle board with 2 mm thick matching PVC edge banding</p> <p>Flip open-Aluminium powder coated flip open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets</p> <p>Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN & electrical cables</p> <p>Metal Legs: Metal legs as per selection of shapes & powder coating</p> <p>Modesty panel :Prelaminated MDF/particle board with exposed edges 2 mm th matching PVC edge banding</p> <p>Glass divders-8 mm th Lacquered glass with 300 mm height fixed with approved bracket / holder</p> <p>Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, inclusive of Vertical / Horizontal ready made raceway for Cables, placing at all floors and for all leads, all accessories as described in item description. As approval of EIC. All the work complete as per the detailed drawing , mock-up sample and instruction of Architect/EIC. Work complete as per the instruction of EIC.</p>	3.00	Nos	0.00	0.00
139	<p>Workstation : 1500x600x1050 (Ht: 750 mm workstation + 450 mm Glass).</p> <p>" -----Do-----as per above specification for complete work .</p>	30.00	Nos	0.00	0.00
140	<p>Keyboard : Providing and fixing key board as per approved make. Metal keyboard tray with Outer Dimension of the Keyboard tray is 507 x 245mm made of 1mm thick CRCA as per approved shade powder coating fixing with require all necessary accessories etc complete</p>	33.00	Nos	0.00	0.00
141	<p>CPU stand : Providing and fixing CPU trolley ebco or eqvilant approved make. CPU Trolley base is made of 1.6 mm thck CRCA and the sides are made of 1.2mm thick. The width of the trolley can be varied to accompany various width CPU. The CPU is mounted on lockable castors.</p>	33.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
142	<p>Pedestal Unit: @400x470X545 MDU: Made up of with prelaminated MDF/particle board and all exposed edge finish with 2 mm th matching PVC edge banding. Hardware make hettich/haffle or equivalent. Providing 3 no's drawers with profile handle as per selection including locking arrangement</p> <p>Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. As approval of EIC. All the work complete as per the detailed drawing , mock-up sample and instruction of Architect/EIC. Work complete as per the instruction of EIC.</p>	33.00	Nos	0.00	0.00
143	<p>4'ft height storage: 450 mm Depth</p> <p>Storage unit top made up of 25 mm thk MDF Exterior grade The top has a post formation round edge finish with both side laminate .Storage body is made of 18mm thick MDF top with exterior grade finish with both side 1 mm th laminate . Shutter finish with both side 1 mm th laminate. The back of the unit is made from 9mm prelaminated board. All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. Having premium lock with wave key technology and side and hinged shutters are sealed with 2mm thick PVC edge banding.SS 304 recessed handles are provided for easy opening and closing of shutter. The units are assembled by knock down fittings such as Minifix & Dowels. All the hardware and Hinges are from Enox/Ebco. PVC edge banding are imported from Rehau or Dolken of Germany .Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, monocoat polish, placing at all floors and for all leads, all accessories as described in item description. As approval of EIC. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC. Work complete as per the instruction of EIC.Contractors shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client Equivalent to VNR series laminate.</p>	19.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
144	<p>Full Height Storage with Laminate Finish : 450 mm Depth Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect. Solid Shutter : 25 mm thick comprising from IS 303 BWR ply & finish with 1 mm thick Laminate . Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate. Ledge/Niche comprising from HDF / Lacquered glass finish w, required lighting arrangement. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives , grooves , consumable hardware & required SS 304 grade hardware/accessories , Profile handle, Wooden frame, monocoat polish, pvc edge banding of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	35.00	Sq.mt	0.00	0.00
145	<p>Overhead storage: " -----Do-----" as per above specification for complete work.</p>	2.00	Sq.mt	0.00	0.00
146	<p>Vanity counter Storage with VNR laminate finish: " -----Do-----" as per above specification for complete work . Using 1 mm thick VNR laminate instead of Veneer. Basic Rate of VNR laminate is Rs.50/ Sq.ft</p>	2.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
147	<p>Pantry below storage : Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be inclusive of shelf both side laminated finish and as per detail drawer unit with SS 304 grade kitchen basket as per selction by architect The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	6.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
148	<p>Pantry above storage -350DX600 H: Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure aand both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm. The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	5.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
149	<p>Glass profile storages : Equivalent to Amardeep/Godrej/Civom/Methodex/EPL/Wipro or approved brand by Architect/Client. Frame: Frame shall be made of IS 303 BWR grade ply 35 mm thick with both side laminate finish as per approved sample. Shutter : 4 mm thick clear glass as per approved sample. Shelves : IS 303 BWR grade ply 25 mm thick with both side laminate finish as per approved sample(adjustable shelving system) Back : IS 303 BWR grade ply 19 mm thick with both side laminate finish as per approved sample. Two side Postforming edge and other side 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. Having premium lock with wave key technology and side and hinged shutters are sealed with 2mm thick PVC edge banding. SS 304 recessed handles are provided for easy opening and closing of shutter. The units are assembled by knock down fittings such as Minifix & Dowels. All the hardware and Hinges are from Hettich/Ebco. PVC edge banding are imported from Rehau or Dolken of Germany . Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories, sample mockup etc as described in item description. work complete as per the instruction of Client/EIC.</p>	2.00	Sq.mt	0.00	0.00
150	<p>Cabin Center Table: @750 x 750 x 400 mm Center table : 25 mm thick Solid wooden top with matt finish monocoat polish. Vertical support: solid wood Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing , all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	1.00	Nos	0.00	0.00
Total Amount					0.00
D	Part-4				
151	<p>Corner table : 450 x 450x 400 mm " -----Do-----" as per above specification for complete work.</p>	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
152	<p>Waiting area Center Table: 900 x 900 x 400 mm Table top: 4mm thick veneer with base ply finish with polish. Vertical support: solid woode Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing , all necessary hardware and fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	2.00	Nos	0.00	0.00
153	<p>Corner Table: 450 x 450x 400 mm " -----Do-----" as per above specification for complete work.</p>	3.00	Nos	0.00	0.00
154	<p>Conference room / Meeting room Drawer & TV Unit : 1500x 510 x 400 mm Providing & fixing TV drawer unit as per detail shape & size with require accessories Top 35 mm thick comprising from 12 mm th IS 303 ply & veneer finish with matt finish monocoat polish, Storage body is comprising from 19mm 303 BWR ply with veneer finish and inner side 1 mm th laminate finish including require nos of drawer with all type of fittings, cutout for air cerculation, require fixtures, hardware Hettich/Haffle make etc complete. SS 304 grade conceal handle shall be provide as per approved selection & detailed drawing and instruction of Architect/EIC. The work shall be done as per the approved specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. The unit shall be manufactured in parts and these parts shall be assembled at site. Basic rate of teak veneer is 120 /Sqft</p>	2.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
155	<p>Waiting Sofa (One Seater) : @ 900(L) x 870 mm (B) x 800 mm (H) comprising up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</p>	2.00	Nos	0.00	0.00
156	<p>Waiting Sofa (three Seater): 2100mm (L) x 870 mm (B) x 800 mm (H) made up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density thikness & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish.The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</p>	3.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
157	<p>Cabin Sofa (Two seater): 1500 (L) x 870 mm (B) x 800 mm (H): comprising of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</p>	1.00	Nos	0.00	0.00
158	<p>Cabin Sofa (One seater): 900 (L) x 870 mm (B) x 800 mm (H) " -----Do-----" as per above specification for complete work. Basic Rate of Fabric : 800 Rmt</p>	1.00	Nos	0.00	0.00
159	<p>Planter box: Providing making, fixing as per detail drawing and required length and depth shall be made from 19mm IS 710 BWP ply with both side laminate finish and providing lighting arrangement cutout and fixing as per detail drawing and instruction. Rate shall inclusive all necessary hardware and fitting, ms framing, paint. The work shall be done as per the specifications, sample approved and as directed by the Architect/ Client. Rate shall inclusive of providing mockup sample for approval of Architect/ Client. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessorie, sample mockup etc as described in item description.work complete as per the instruction of Client/EIC.</p>	5.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
160	<p>Chair Type- 1A - Model equivalent make - HOF MAR-1003 High Back :</p> <ul style="list-style-type: none"> * Chair in Moulded Ply with Head Rest. * Double Cladding. * High Density PU Foam in Seat & Back. * Chrome Arms & Cushion on it. * Multi Tilt Mechanism. * Chrome Base & Gas Lift. <p>Work complete as per the approved sample & instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.</p>	2.00	Nos	0.00	0.00
161	<p>Chair Type-2A -Model equivalent make - HOF MAR-1004 Mid Back</p> <ul style="list-style-type: none"> * Chair with Moulded Ply in Seat and Back. * PU Moulded foam on Seat & Back. * Adjustable Arms with PP cladding. * Chrome Base. * Synchronized Mechanism & Gas Lift. <p>Work complete as per the approved sample & instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.</p>	16.00	Nos	0.00	0.00
162	<p>Chair Type-3A -Model equivalent make - Amardeep Lotus 01 High Back</p> <p>Model equivalent to Lotus 01 : High Back Revolving Chair as per approved make list.</p> <p>Chair With frame in MS, PU foam in back & Moulded PU Seat, Chrome Arms with PU cladding & Synchro Mechanism, Chrome base, & Gas Lift.</p> <p>Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	7.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
163	<p>Chair Type-4A -Model equivalent make - Amardeep Lotus 02 Mid Back Model equivalent to Lotus 02 : Medium Back Revolving Chair as per approved make list. Chair With frame in MS, PU foam in back & Moulded PU Seat, Chrome Arms with PU cladding & Synchro Mechanism, Chrome base, & Gas Lift. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	24.00	Nos	0.00	0.00
164	<p>Chair Type-5A (Other area Chair) -Model equivalent make - Model equivalent to Vento 02 : Mid Back Revolving Chair as per approved make list. Chair With frame in MS, PU foam in back & Moulded PU Seat, Chrome Arms with PU cladding & Synchro Mechanism, Chrome base, & Gas Lift. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	40.00	Nos	0.00	0.00
165	<p>Chair Type-7A (Training room Chair) : Model equivalent make -to Dx06(c) Amardeep as per approved sample list. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	6.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
166	<p>Art work: Providing and fixing in position commissioned art works inside the building on the wall or ceiling and extension of the same till floor/ceiling. The composition of the commissioned art work shall be from any type of wood, metal like copper, brass, SS, MS, fabric, acrylics, rubber, plastic, tough boards, cementitious boards, fibers, gypsum, POP etc. all. The form of material may also very based on material properties like sheets, wires, blocks, inclusion of cutouts, bending of the materials, profile cutting an shaping of the materials, manufacturing at site as well as at site, covering the prepared material by means of the bubble sheets, jute bags or in wooden packing materials. The commissioned art work may require any shade, finish and texture of duco painting, specialty painting, PU painting, general painting to paintable surfaces, galvanizing, powder coating, anodizing etc. The base surface where the commissioned art work is to be installed also needs some modification to enhance the effect of art works. The use of material like fiber glass wool/ boards, filler fabric, mounting material may also essential based on the design of the art work by artist. The rate shall be inclusive of any type of lighting features to be added into it includes LED lights, neon lights including its supporting and suitable wiring for the same within the art works. Only one electrical control point connection will be given as close to art works. The rate shall be inclusive of making necessary provisions within the commissioned art works of fixing of the same. The provisions of the fixing of the art work may be in parts but it shall be inclusive of the all arrangements like LN key, studs, anchors, nuts and bolts etc. all.. The concept of the art work will be generated by architect and interior designer and based on that offers from the artists to be invited for design and execution of the artwork. The selection of the artist is to be done by architect and interior designer only. Main contractor is bind to follow the methodology suggested by architect and interior designer to be followed for development of commissioned art work. The overall outline area covered by art work is to be considered for the measurement instead of actual area of art work. Deductions of the internal cutouts, spaces in between of the art work shall not be made. Since there is huge variance in types of the commissioned art works, the same is to be completed in all respect inclusive of the materials and methodology is stated above and may not be. For any additional materials, process, methodology no extra payments shall be made. The quotations of the artist shall be got approved in advance including area of the proposed art works. Total payment of the artwork will be done as per basic rate and difference between actual cost per sqm and basic rate per sqm will added or deducted without any consideration of the, overhead and profit over the difference. It is the responsibility of the main contractor to provide scaffolding, power, water, facilitating the areas required for developments and storage of the art work etc. The protection and cleaning of the pre and post installation of the art work is the responsibility of the main contractor.</p>	25.00	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
167	Wooden benches (3 seater) at passage area. size: 1500mmx 450mmx 450mm : Providing, making, and placing in position with all necessary accessories. Seat, Back & Base: wooden/ply 25 mm thick with Polish finish and 40 density PU foam with fabric finish as per selection of architect. All wooden surfaces are to finished with PU polish. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per drawings, specifications & instruction of Client/EIC. seating made from 40 density PU foam with fabric finish as per selection of architect	1.00	Nos	0.00	0.00
168	Signages : Providing and fixing signages comprising form 45mm aluminum profile with back side UV printed PC as per instruction of Archiect/EIC. Contractor shall submit mock up sample.	3.00	Sq.mt	0.00	0.00
169	Emergency Signages : Providing and fixing emergency signages of size 300mm x 100mm comprising form 1.5mm thick photoluminescent tap on 3mm thick acrylic sheet as per instruction of Archiect/EIC. Contractor shall submit mock up sample.	6.00	Nos	0.00	0.00
170	Logo Work : Providing and fixing standard Logo using virgin acrylic or other material like Colored HDF/cementsheet /SS plate with CNC work complete as per architect selection , letters as per detailed drawings and fixed with approved adhesive with necessary fittings and provision shall be made for conceal LED light as per detail drawing. (logo size will be aprox. Size - 600 mm dia)	1.00	Nos	0.00	0.00
171	Supplying and fixing Brass Emblem With accessories as per requirement of Architects and Engineer in charge.	1.00	Nos	0.00	0.00
172	Trap Door : 12.5mm thick Gypboard® Plain Providing and fixing trap door as per approved sample of Ceiling panels comprise of a Aluminum Alloy 6063 T6 Extrusione (Powder coated) with MR gypsum Board . Each panel features a push- latch closing mechanism with door retaining safety cable & hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, etc. complete work. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price. 600 x 1200 mm	10.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
173	Carpet Flooring Work: Providing & laying carpet flooring as per approved make & Sample by Architect. Carpet fixed with SR 505 Pidilite or equivalent tile adhesive and underlay foam material. carpet should be laid as closure to each other. Contractor will take care for level matching with other area flooring. Scope includes labour, under lay material, disposal of debris, necessary cutting of tiles without damaging the edges, and at require area provide 304 ss finish end profile to protect and cleaning, etc. complete. All works are carried as per detail drawing / instruction of architect / EIC. Before laying carpet contractor shall prepare even surface as per required. equivalent Welspun Relay 2.0 Carpet tiles or basic rate of carpet is Rs. 220/Sqft	69.00	Sq.mt	0.00	0.00
174	Texture paint : Wall painting two coats with Stucco of Asian or equivalent approved brand in any shades and colour as directed on wall surface to give an even shade including applying of a one coat of Penetrating primer or equivalent and two coats of paint, scaffolding to at any height with all labour and material thoroughly brushing the surface free from mortar droppings and other foreign matter and sand prepared smooth etc. complete. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer / paint application is to be done with the rollers. rate shall be including, safety measures, crack filling and levelling as per manufacturers specification. Top coat should have. 1) Low VOC content. 2) Crack Bridging ability upto 2.6 mm. 3) 100% pure acrylic emulsion 4) Anti-Carbonation concrete protection 5) Very Low Flame spread 6) Superior Washability	10.00	Sq.mt	0.00	0.00
175	Metal Profile : Providing and fixing of 6 mm thick S.S. T Profile Copper or as per approved sample by Architect including necessary material, adhesive tools, tackles, fittings etc complete. Work complete including all type of tools, tackles, scaffolding, mock sample, etc complete as per instruction of Architect/EIC.	50.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
176	<p>Server Rack Console : Providing & fixing server rack Console complete as per drawing/Ref Image. made from up of 19 mm thick BWR grade ply & finished of 4 mm thick veneer of approved shade with monocoat polish as per drawing. Rate shall be inclusive of providing, fixing all necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Rod locks, Multipurpose lock, Rate shall be inclusive of internal shelves of 19mm thick IS 303 BWR ply and laminate , PVC edge beading . All external & internal exposed woodwork to be finished in PU semi gloss paint finish polish as per specified items manufacturer's specifications. Basic rate of veneer 120/- Sft.</p>	7.00	Sq.mt	0.00	0.00
177	<p>Custmised wall painting: Canvas painting with frame work : Providing making painting/polishing and Fixing in position of wooden frames having profile as per drawing and sizes as specified for paintings with card board mounting /canvas frames including backing of required thickness of hardboard / ply board(IS 303 BWR) backing. Frame shall be hanged on the wall using key hole chaplas fixed at the back part of the frame at all heights, all floors and all levels. The rates shall be inclusive of all material, labour, wastage, antitermite treatment, polishing all tools tackles etc complete. Sample of the frame shall be got approved by Architect prior to manufacturing on large scale. D) Wooden Frames for Canvas Work as per drawings: Frame Size - 75mm x20mm Wood Work - Burma Teak Wood Frame shall be finished with PU polish work. The art work shall be hanged on the wall using heavy duty approved key-hole chaplas</p>	15.00	Sq.mt	0.00	0.00
178	<p>Artifacts: Providing and supplying Artifacts as per selection . Glass/Metal/Fiber/Ceramic. Basic rate of Artifacts: Rs. 2500/ Nos. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	15.00	Nos.	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
179	Artificial Planter/ indoor plant with SS finish pot as per approved sample. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	10.00	Nos	0.00	0.00
180	Pot with Trolly 35 : Supply & installation of High quality rotomoulded plastic which is UV resistant, light weight yet strong and durable, frost resistance, unbreakable and easy to move , Matte finish is perfect for resisting scratches, dirt, and fingerprints. Unique bottom channel design with optional drainage holes and hidden groves/handles for easy lifting are available in this pot as per approved sample by Architect. Work complete including all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per detailed drawings, specifications & instruction of Client/EIC.	25.00	Nos	0.00	0.00
181	Pots Chatura 9' : Supply & Installation of Snack Plant Pots Chatura 9' Durable plastic planter made of high-grade plastic that can be reused for years and then recycled to avoid plastic pollution. as per approved sample plant by Architect. Work complete including all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per detailed drawings, specifications & instruction of Client/EIC.	30.00	Nos	0.00	0.00
182	Monstera plant : Supply & Installation of approved sample plant by Architect. Work complete including Poting mix , Expended Eca - 8 mm to 15 mm , all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, maintenance with 30 days or more till the shrubs forms a thick etc etc complete as per detailed drawings, specifications & instruction of Client/EIC.	30.00	Nos	0.00	0.00
183	Bird of paradise Plant : Supply & Installation of approved sample plant by Architect. Work complete including Poting mix , Expended Eca - 8 mm to 15 mm , all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, maintenance with 30 days or more till the shrubs forms a thick etc etc complete as per detailed drawings, specifications & instruction of Client/EIC.	10.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
184	Snack plant : Supply & Installation of approved sample plant by Architect. Work complete including Potting mix , Expanded Eca - 8 mm to 15 mm , all type of material, fittings, fixtures, Finish, loading , unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, maintenance with 30 days or more till the shrubs forms a thick etc etc complete as per detailed drawings, specifications & instruction of Client/EIC.	20.00	Nos	0.00	0.00
185	Corner Guard: Providing and fixing 1.2mm thick & 14mm high Stainless Steel profile corner guard (304 grade) with powder coated of approved make list or as selected by Architect. All joint sealed with approved sealant approved shade and colour in proper line as per detailed drawing/ instruction and approval by architect. work complete including all type of fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client.	7.00	Rmt	0.00	0.00
186	Compactor storage : Providing and fixing of mechanically moveable Compactor unit Kompres, Godrej, Haworth or equivalent make as per approved sample. With 4 level making 5 storage compartment vertically, using 12 bend shelves as per drawing Capacity 50 & 60Kgs. UDL /Compartment. Each Mobile Unit will have Mechanical arrangement Each Component of the System will be treated with rust preventive treatment and will be powder coated as per approved sample. Rate shall inclusive of mock up sample, all materials, floor rail , shutter , loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the approved Shop drawing , mockup sample and instruction of Architect/Client. a) Double face Mechanical Unit : 2085 X 630 X 2130	8.00	Nos	0.00	0.00
187	b) Single face Mechanical Unit :2085 X 400 X 2130	1.00	Nos	0.00	0.00
188	c) Single face Fixed Unit : 2085 X 340 X 2130	1.00	Nos	0.00	0.00
189	d) Double face Mechanical Unit : 3620 X 630 X 2130	8.00	Nos	0.00	0.00
190	e) Single face Mechanical Unit : 3620 X 400 X 2130	1.00	Nos	0.00	0.00
191	f) Single face Fixed Unit : 3620 X 340 X 2130	1.00	Nos	0.00	0.00
192	g) Double face Mechanical Unit : 5900 X 630 X 2130	5.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
193	h) Single face Fixed Unit : 5900 X 340 X 2130	1.00	Nos	0.00	0.00
194	i) Shutter : 5 Nos	5.00	Nos	0.00	0.00
195	j) Double face Mechanical Unit : 2715 X 630 X 2130	3.00	Nos	0.00	0.00
196	k) Single face Fixed Unit : 2715 X 340 X 2130	1.00	Nos	0.00	0.00
197	l) Shutter: 3 Nos	3.00	Nos	0.00	0.00
198	m) Double face Mechanical Unit : 2085 X 630 X 2130	6.00	Nos	0.00	0.00
199	n) Single face Fixed Unit : 2085 X 340 X 2130	1.00	Nos	0.00	0.00
200	o) Shutter : 2 Nos	2.00	Nos	0.00	0.00
Total Amount					0.00
E	Part-5				
201	<p>Existing compactor remove & Reinstallation work (Removing of First floor B wing & Shifted first floor A wing) : Re – erection of the System in as it is condition. Testing & commissioning and handover. If any parts are missing or damaged the work will need to be completed at no extra payment</p> <p>5500 X 650 X 2000 mm - Double Face Mechanical Unit - 15 Nos ,</p> <p>5500 X 320 X 2000 mm -Single Face Fixed Unit :01 Nos.,</p> <p>SHUTTER - 05 Nos</p> <p>Work complete including all type of material, fittings, fixtures, Finish, loading , unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, necessary frame work, equipment etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	1.00	Job	0.00	0.00
202	<p>ELECTRICAL WORK: Point wiring for Light / Bell with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in/ on surface on wall/ceiling complete with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories CAT III</p>	180.00	Pt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
203	Point wiring for secondary light point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling, complete with earth continuity and necessary connection with primary light with accessories erected on Metal / PVC box covered with 3 mm thick PC(Polycarbonet) / Acrylic sheet for open / concealed wiring. with necessary Lamp holder / ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories	125.00	Pt	0.00	0.00
204	Point wiring for Two Way Controlled Light Point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of .ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling ,complete with 6A Modular type switches and following type of accessories erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary batten/angle holder or ceiling rose or H.D.Connector as directed CATIII	20.00	Pt	0.00	0.00
205	Point wiring for FAN with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling complete with 6A Modular type switch and hum free EME four or more step type electronic fan regulator with separately mounted and accessories with earth continuity of following type erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories.CAT III	15.00	Nos	0.00	0.00
206	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge. (23)USB Charger with output of 5 V DC,2.1 A with inbuilt surge protection. Cat-III	30.00	Ea	0.00	0.00
207	Point wiring for Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling with following type accessories. CAT III	40.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
208	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. For 6A Plug with 2-1.5 sq.mm Cu. Wire with medium class Rigid PVC pipe and accessories CAT III	50.00	Pt	0.00	0.00
209	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.[III] For 16A Plug with 2-2.5 sq.mm Cu. Wire (a) with medium class Rigid PVC pipe and accessories.CAT-III	10.00	Pt	0.00	0.00
210	Providing & erecting Switch board for Computer or electric apparatus consisting of following items in single board erected on PVC / Metal board with 3 mm thick PC (Polycarbonate) / Acrylic sheet erected as directed for [B] modular type accessories 1 no. 6A/16A universal plug-switch combined. CATIII 2 nos. 6A Switch & 2 nos 16A Switch 2 nos. 6A 5 pin Plug & 2 nos 16A Socket	59.00	Ea	0.00	0.00
211	Providing & Erecting eight module pop up floor box/flushed with table surface Conform to IEC 60670-1, IEC 60670-23 & IEC 60884-1 with required items as demanded by engineer in charge with complete finishing .cat-III	49.00	Ea	0.00	0.00
212	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (a) 2 wire 1.5 sq. mm	1100.00	Mtr	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
213	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (B) 2 wire 2.5 sq. mm	4600.00	Mtr	0.00	0.00
214	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected in / on wall / ceiling with 2.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size. (a) with medium class Rigid PVC pipe and accessories (A) 2 wire 4 sq. mm	1600.00	Mtr	0.00	0.00
215	Supply, Installation, Testing and Commissioning of suitable sweep, BEE 5 Star rated, Ceiling fan with Brush Less Direct Current (BLDC) permanent ferrite magnet Motor, class of insulation: B, Rust free 3 nos. Aluminium blades, 2 nos. canopies, shackle kit with earthing provision, copper winding, Power factor not < 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM, 230v (tolerance as per IS : 374-2019), THD < 10%, with remote unit for Speed Control and all remaining accessories including safety pin, nut bolts, washers, temperature rise = 75 degree C (Max.), suitable for 140 to 285 Voltage and rectifier circuit with surge, over current and overload protection, 50 Hz, Single phase AC Supply, earthing etc. Complete as required. [Make shall be approved by Engineer in Charge] (A) 900 mm sweep (36")	2.00	Nos	0.00	0.00
216	Supply, Installation, Testing and Commissioning of suitable sweep, BEE 5 Star rated, Ceiling fan with Brush Less Direct Current (BLDC) permanent ferrite magnet Motor, class of insulation: B, Rust free 3 nos. Aluminium blades, 2 nos. canopies, shackle kit with earthing provision, copper winding, Power factor not < 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM, 230v (tolerance as per IS : 374-2019), THD < 10%, with remote unit for Speed Control and all remaining accessories including safety pin, nut bolts, washers, temperature rise = 75 degree C (Max.), suitable for 140 to 285 Voltage and rectifier circuit with surge, over current and overload protection, 50 Hz, Single phase AC Supply, earthing etc. Complete as required. [Make shall be approved by Engineer in Charge] (B) 1200 mm Sweep (48")	15.00	Nos	0.00	0.00
217	Providing 2.5mm.thick laminated acrylic sheet to cover the fan hook or Fan box.	15.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
218	Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected duly painted for fan complete with necessary 24/ O.20, 3 core flexible wire with earthing.	15.00	Mtr	0.00	0.00
219	Supplying & erecting fan hook box of 10 mm M.S. round bar bounded to the RCC bars up to 50mm length each side and pierced through a 16 Gauge M.S. box / Heavy Duty PVC box complete erected concealed in Ceiling with necessary finishing.	15.00	Nos	0.00	0.00
220	Supplying & erecting approved make low noise decorative Exhaust fan having size 200mm with 1350 RPM with square frame ABS body with inbuilt lowers & square frame.	3.00	Nos	0.00	0.00
221	Supplying & erecting Electronic Type Cordless Call Bell erected on PVC/Metal board having portable bell push working on D.C. & bell on 230V A.C. supply with cells / battery	1.00	Ea	0.00	0.00
222	Supplying & erecting Approved make call bell indicator with buzzing sound and Red light indicating lamp with Red light button to attend the call suitable for 240 v 50 c/s supply to be erected.	1.00	Ea	0.00	0.00
223	<p>Axeon Linear Profile: 30W 4ft, High efficiency long life Linear suspended luminaire with white powder coated finish extruded aluminium housing. 51mm width, 85mm height Special translucent satin finish colour LED PMMA Diffuser. LED driver duly wired up to terminal block for easy installation and long service. Luminous efficacy not less than 115lm/W. CRI>80, IP20, Ambient temp-0 to 45DegC, Driver efficiency>85%, THD<10%, CCT- 5700K, 50,000 hrs @ L70 life, Powerfactor>0.95, Surge protection-3 kV, Multistage Isolated Constant Current operated driver with range 140-300V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard.</p> <p>Luminaire lumen ≥ 3450lm. Available in continuous as well as standalone configuration. LM34-401-XXX57WG2L</p>	15.00	EA	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
224	<p>Axeon Linear Profile: 30W 4ft, High efficiency long life Linear recessed luminaire with white powder coated finish extruded aluminium housing & continuous option with 56 mm Width & 86 mm Height. Special translucent satin finish colourLED PMMA Diffuser. LED driver duly wired up to terminal block for easy installation and long service. Luminous efficacy not less than 110lm/W. CRI>80, IP20, Ambient temp-0 to 45DegC, Driver efficiency>85%, THD<10%, CCT- 5700K, 50,000 hrs @ L70 life, Powerfactor>0.95, Surge protection-3 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 150-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen ≥ 3300lm. Available in continuous as well as standalone configuration. Wipro Model - LM34-401XX-57RMCG1</p>	45.00	EA	0.00	0.00
225	<p>Gimball LED Downlight: 10W, High efficient recess mounted COB LED round downlighter with extruded aluminium housing. High efficiency reflector optics for effective thermal management using aluminium casting. CRI>80, CCT - 5700K,50,000 hrs @ L70 life. IP20, Ambient temp-0 to 45DegC, Driver efficiency>85%, THD<20%, Powerfactor>0.95, Surge protection-3 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 120-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Cutout Dia-ø135mm. Luminaire lumen ≥ 1000 lm. (100 lm/W). Wipro Model LD56-141-036-57-XX</p>	20.00	EA	0.00	0.00
226	<p>MOLLIS X LED DOWNLIGHT: 18W, High efficient deep inset recess mounted LED round downlighter with white powder coated, pressure die cast aluminium housing. High transmittivity PS diffuser provides soft light UGR<19. CRI>80, IP40(Housing),IP20(Driver), Ambient temp-0 to 45DegC, CCT - 4000/5700K, 50,000 hrs @ L70 life.Driver efficiency>85%, THD<10%, Powerfactor>0.95, Surge protection-2.5 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 100-265V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen ≥ 1800 lm. (100 lm/W), Wipro Model No.LD06X-221-XX-57-XX</p>	140.00	EA	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
227	<p>PICASSO CORAL LED: 30W, High efficient coral (bell) shape made of aluminium white colour coated outside finish Upto 1m suspension. LED's provided with high efficient non yellowing PMMA diffuser provides soft light.CRI>80, IP20, Ambient temp-0 to 45 Deg C, CCT - 4000K, 50,000 hrs @ L70 life. Driver efficiency>85%, THD<10%, Powerfactor>0.95, Surge protection-4 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 150-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen \geq 3000 lm. (100 lm/W), Wipro Model No. LM56-301-XXX-40-WH</p>	4.00	EA	0.00	0.00
228	<p>IMMACULATE 2X2 Recess Integral, SMD 2x2 LED, IP 20, 36W LED Recess mounted fixture with System efficacy of more than 100lm/W and system lumen output 3600lm. Luminaire shall have satin finished translucence (HET) diffuser for Uniform illumination and wider light distribution. LM 80-08 compliant LEDs from reputed makes such as Nichia / Cree / Bridgelux / Lumileds should be provided. LEDs used in the product shall comply with EN 62471 for Photo-biological safety and certificate for the same from manufacturer shall be provided. Luminaire shall use SMD type LED. The LED shall be compliant with LM80-08 standard with L70 life of 50000 Hrs tested at maximum current (Complete LM 80 test report for LED should be submitted for 10000 hrs of testing). The LEDs used should be with CCT of 5700 K and CRI of Minimum 80. LED Driver shall be Multistage, Isolated type, APFC, Constant Current topology driver with proper heat sink for heat dissipation suitable to operate in input voltage range of 140V to 300V (nominal rated voltage – 240V) with 3KV internal surge protection, Power factor greater than 0.95 and total harmonic distortion (THD) of less than 10% should be integral to the luminaire. Complying to SELV < 60V DC standards. Compliance to Indian Standards of IS10322 Part 5 / Sect 1:1967; 16105 : 2012; IS 16106 : 2012; IS 15885 (Part2/Sec13) : 2012; IS 16108 : 2012 Wipro Model No.CRCO10R036HP57G3.</p>	45.00	EA	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
229	<p>TrimLED Neo: 20W High efficient LED batten surface/wall mounted Specially designed extruded Aluminium housing with PC diffuser. In-built electronic driver duly wired up to terminal block.IP20, CRI >80, Temperature range-0 to 50DegC, Driver efficiency>85%, Power factor>0.9, CCT - 6500K, THD<20%, Surge protection 2.5kV, 50000 burning hours as per L70 Criteria, Multistage Isolated Constant Current operated driver with range 180-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen \geq 2000 lumens (100 lm/W):Wipro Model No. LL20-221-XX-65ALNE</p>	3.00	EA	0.00	0.00
230	<p>Tisva Wooden hanging Light Supply, Installation, Testing & Commissioning of Pendant Mounted luminaire 25~35W LED system power, 1)lumen package shall be minimum 3500 lumens keeping 100lumen/watt minimum 2)colour temperature of 4000\pm500k, CRI>80 3) 230V constant current driver, 70% of luminous flux after 50,000 operating hours, energy efficient LEDs, 4) direct light emission, aluminium housing with polyester powder coat aluminium white applied over a 5-stage pre-treatment, 5) prismatic diffuser for glare-free uniform illumination, Electronic Control Gear, Protection class I, IP20, 6)Approx Dimensions \varnothing = 430mm, H = 75mm, Mounting pitch = 100mm Hanging wire - 800mm , 7)LED shall be from Cree/Nichia/Philips Lumi Leds/ Osram/seoul/bridgelux. 8)Fixture should be available in wooden finish 9) Fixture selection will be subject to sample approval by client & architect consultants keeping above specs as base. % THD shall not exceed 10% . Lighting technologies Drumlit suspended 30w Equalant in Philips/Wipro/Tivsa/Havells/Lighting Technologies</p>	3.00	EA	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
231	<p>50MM PROFILE LIGHT</p> <p>"Supply Installation Testing Commissioning of Indoor recess mounted 50mm cut out (50x35mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continuous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture \geq100 Lumens/Watt</p> <p>Wattage should be 30-35w/m . Should have a dotless continuous effect. Should be operated using remote driver of 24V Dc only, kept at suitable locations for future maintainance.</p> <p>Approved Make.: WIPRO/TISVA/HAVELLS/LIGHTING TECHNOLOGIES/PHILIPS"</p>	25.00	RMT	0.00	0.00
232	<p>35MM PROFILE LIGHT</p> <p>"Supply Installation Testing Commissioning of Indoor recess mounted 35mm cut out (35x35mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continuous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture \geq100 Lumens/Watt</p> <p>Wattage should be 27-33w/m . Should have a dotless continuous effect. Should be operated using remote driver of 24V Dc only, kept at suitable locations for future maintainance.</p> <p>Approved Make.: WIPRO/TISVA/HAVELLS/LIGHTING TECHNOLOGIES/PHILIPS"</p>	20.00	RMT	0.00	0.00
233	<p>Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, conforming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used)</p> <p>(F) Single phase 8 way SS Double door</p>	1.00	Each	0.00	0.00
234	<p>Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, Conforms to IS 8623-1 & 3, IEC 61439-1 & 3 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) suitable for. (A) single phase incoming and horizontal single phase outgoing. (iv)Single phase 12 way SS Double door</p>	2.00	Each	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
235	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 6 way SS Double door for horizontal single phase outgoing	1.00	Ea	0.00	0.00
236	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 8 way SS Double door for horizontal single phase outgoing	4.00	Ea	0.00	0.00
237	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat.III	110.00	EA	0.00	0.00
238	Providing & erecting 240 V MCB double pole switch for lighting Load (B Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (B) 40 Amp. Cat.III	2.00	Ea	0.00	0.00
239	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp.	2.00	Ea	0.00	0.00
240	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (B) 40 Amp.	4.00	Ea	0.00	0.00
241	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (a) 6 to 32 Amp. Cat.III	4.00	Ea	0.00	0.00
242	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (b)40 Amp. Cat.III	4.00	Ea	0.00	0.00
243	Providing & erecting 415V MCB Four Pole Switch for Lighting Load (B curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (b)40 Amp. Cat.III	26.00	Ea	0.00	0.00
244	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity C) 63 Amp. CAT-III	6.00	Ea	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
245	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 25 Amps.DP Cat. III	3.00	Ea	0.00	0.00
246	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 40 Amps.DP Cat. III	16.00	Ea	0.00	0.00
247	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 63 Amps.DP Cat. III	8.00	Ea	0.00	0.00
248	Providing & erecting weather proof, dust & vermin proof, floor mounted front operated indoor type cubical panel board necessary IP-42 and above protection as per approval from engineer incharge made from 14 SWG thick CRC M.S. sheet for outer body & doors, 16 SWG thick CRC M.S.sheet for internal partitions with necessary accesories , supporting angles/ flats channel including cutting, bending, drilling, welding, riveting with internal partitions & cable alley as per requirements & instruction of engineer-in-charge with erection of supplied switch gears, BUSBARS, suitable size of inter connecting PVC copper wire / copper-aluminium strips, rubber grommets, rib, bakelite control fuses/MCB for measuring instruments, earth bus & earth bolts, foundation flange - bolts-base Plates, sufficient nos. of hinged doors, handles with locking arrangement and rubber gasket,heavy duty end terminal connection,danger notice board,necessary ventilation,earthing strip complete. The Panel shall be painted with epoxy powder coating. (The rates excludes the cost of switchgears, bus bars, inter connecting mains & Copper Aluminium strips, meters, Fuses etc. The dimension shall be measured excluding base beams) The panel shall be supplied with following approved manufacturers with following size.(B) The standard companies switch gear shall be used and only manufacturers at CPRI approved factory. (i) with 350mm depth	4.00	Sq.Mtr	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
249	Supplying and erecting triple pole & neutral 440V/ 500V panel mounting Aluminium Busbars with four equal Nos. of bus having current density not more than 0.8 Amp. / sq.mm (Rated current / cross section area) duly wrapped with colour insulating tape for phase sequence of following current carrying capacity, erected with necessary bus bar supports /insulators, main cable socket to each busbar,erected in existing cubical panel with necessary connections.(A) Suitable for 100 Amp. Capacity	4.00	Rn.Mtr	0.00	0.00
250	Providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 25 KA. at 415 V, having normal current rating up to 25 A to 100A. with Fixed thermal & magnetic release suitable to work on A.C. supply 50 c/s. with all internal connections, spreader tinned copper & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only Cat III	2.00	Ea	0.00	0.00
	Total Amount				0.00
F	Part-6				
251	Supplying and erecting approved make panel mounting type Digital Voltmeter having 3 digits LED display, 0 to 750 AC Volts range erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	2.00	Ea.	0.00	0.00
252	Supplying and erecting approved make panel mounting type Digital Ammeter having 3 digits LED display, external CT operated, calibrated for 0 to 1000 Amps suitable to operate on 500 Volt AC , erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	2.00	Ea.	0.00	0.00
253	Supplying and erecting Ammeter / Voltmeter selector switch for 3 phase AC Supply 500 V on existing panel board with necessary connections.	2.00	Ea.	0.00	0.00
254	Providing & erecting L.T. Current Transformer with bar primary 50/5 to 1000/5 ratio 15 VA burden erected in existing CRCA box duly secured with insulating materials connected to the meter	6.00	Ea.	0.00	0.00
255	Supplying and erecting approved make suitable panel indicator LED type lamp, lens cover, complete erected with necessary connections.	10.00	Ea.	0.00	0.00
256	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. (D) 3 1/2 core 70 Sq. mm (35 Sq. mm 1/2 core)	200.00	Rmt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
257	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. (A) 3 1/2 core 25 Sq. mm (16 Sq. mm 1/2 core)	50.00	Rmt	0.00	0.00
258	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. A)4 core 16 Sq. mm	600.00	Rmt	0.00	0.00
259	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cables. (A) 4 core 10 Sq. mm	200.00	Rmt	0.00	0.00
260	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cable. (C) 3 core 6 Sq. mm	100.00	Rmt	0.00	0.00
261	Providing and, fixing heavy duty flange type brass double compression type cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (C) 3 & 1/2 core 70 Sq. mm	4.00	EA	0.00	0.00
262	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. E) 2 to 4 core 25 Sq. mm	2.00	EA	0.00	0.00
263	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. D) 2 to 4 core 16 Sq. mm	20.00	Ea	0.00	0.00
264	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (B) 2 to 4 core 6 Sq. mm	4.00	Ea	0.00	0.00
265	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. C) 2 to 4 core 10 Sq. mm	8.00	Ea	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
266	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (E) 70 Sq.mm.	16.00	Ea	0.00	0.00
267	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (C) 16/25 Sq.mm.	160.00	Ea	0.00	0.00
268	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. B)10 Sq. mm	32.00	Ea	0.00	0.00
269	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (A) 1.5/2.5 to 6 Sq.mm	16.00	Ea	0.00	0.00
270	Providing and erecting HOT deep Galvanised iron strip wire 8 to 16 SWG.	20.00	KG	0.00	0.00
271	Providing and erecting required size HOT deep Galvanised iron strip for earthing of H.T. , OCB/ ACB/ Transformer LT panel board, Motors etc. using proper clamp.	50.00	KG	0.00	0.00
272	Providing and erecting required size Copper strip for earthing of H.T. OCB / ACB/ Transformer, LT panel board, Motors etc. using copper clamp.	20.00	KG	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
273	Supplying & erecting in earthpit of minimum bore dia. 225mm size approved make Safe Earthing Electrode consisting Pipe-in-Pipe Technology as per IS 3043-1987 made of corrosion free hot dipped G.I.Pipes having Outer pipe dia of 80 mm having 80-200 Micron galvanising, Inner pipe dia of 40 mm having 200-250 Micron galvanising, connection terminal dia of 14 mm with constant ohmic value surrounded by highly conductive compound with high charge dissipation suitable for following type of applications with chamber and heavy duty cover.(approved make OEM has to submit test certificate including value of earth resistane of installation. [B] For Electrical installation up to 11 KV located in other than normal soil i.e. Soft Rock, Marshy Soil etc. -Length of Pipe : 2 mtr -Back filling Compound :1 no. Bag of 25 Kg.	2.00	Ea	0.00	0.00
274	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (b) 25 mm	4100.00	Mtr.	0.00	0.00
275	Supplying and erecting approved make online Un-interruptible Power Supply system comprising flat cum-boost charger with IGBT base rectifier & Inverter & sealed maintenance free SMF batteries. The charger having operating capacity for input 160-270V AC & inverter having output 230V,50 Hz Ac with 0.8 load power factor with battery, over/under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following power backup.with MS painted batteries stand, 10% Overload capacity for momentary load. (D) 5 KVA with 1Hr Backup	2.00	Ea.	0.00	0.00
276	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..150 X 50 X 1.5 mm Thick	100.00	RMT	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
277	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge.300 X 50 X 1.5 mm Thick	60.00	RMT	0.00	0.00
278	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (3) 150 X 50 X 1.6 mm Thick 90° Elbow	6.00	EA	0.00	0.00
279	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (5)300 X 50 X 2.0 mm Thick 90° Elbow	2.00	EA	0.00	0.00
280	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories,Junction Box,Joints as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III. [10] 150mm x 38mm x 1.6mm with Three Compartments.	100.00	Each	0.00	0.00
281	[12] 250mm x 38mm x 1.6mm with Three Compartments	80.00	Each	0.00	0.00
282	[13] 300mm x 38mm x 1.6 mm with Three Compartments	160.00	Each	0.00	0.00
283	Supply & installation of surface mounted U PVC snap-on adaptable trunking raceways, fabricated out of U-PVC to Off-White or approved shade as per IS 733 of thickness 2.0mm for the base and sides with all accessories like removable covers, joints ,height spacer,angles complete with necessary bends, suitable sized junction boxes and tees etc, Complete. Make MK & Legrand. (a)Size: 50x80mm PVC Raceways for Power & Data with 2 compartments above specifications.	300.00	MTr	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
284	Supply & Installation of AO Smith Z8 Hot+ normal RO Baby-Safe Water Hot Water 10 L Storage 8-Stage Purification 100%RO+SCMT (Silver Charged Membrane Tech.) Wall mount Water Purifier as per approved make & Sample by Architect. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	2.00	Nos	0.00	0.00
285	Supply & Installation of LG 20 L Solo Microwave Oven (MS2043DB, Black).Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	2.00	Nos	0.00	0.00
286	Supply & Installation of VOLTAS Water Cooler FS 150/150 N P ROT R22. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	2.00	Nos	0.00	0.00
287	Supply & Installation of Croma 215 Litres 3 Star Direct Cool Single Door Refrigerator with Anti Fungal Gasket (CRLR215DCD008903, Criss Cross Metallic Grey)Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	2.00	Nos	0.00	0.00
288	ELV WORK: SITC of 4MP Fixed Lens Dome Type Camera, H.265 4MP IR Vandal Proof Dome N/W Camera, 2.8mm/3.6mm, 30M IR, Micro SD, DC12V/PoE, IP67/IK10, Basic IVA, 1 / 2.7" CMOS, 2560 × 1440, 0.01 Lux, F1.2, AGC ON; Defog, True day/night, Digital WDR, 3D DNR, HLC & BLC, Triple streams, Smart codec by ROI, Cyber Security, Basic intelligent video analytics, NDAA Compliance, UL, CE, FCC Certified	20.00	Ea.	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
289	SITC of 5 MP Motorised Varifocal Lens Bullet Camera - H.265 5MP IR Bullet N/W Camera, 25/30FPS, Motorised Varifocal 2.8-12mm, IR up to 70M, Micro SD support up to 128GB, DC12V/PoE, IP67/IK10, Basic IVA, 2 MP resolution (2592 × 1944), True day/night, Digital WDR, 3D DNR, HLC & BLC, Triple streams, Smart codec by ROI, Cyber Security, Intelligent video analytics, NDAA Compliance, UL, WEEE, REACH CE, FCC Certified, IK10 & IP67, Opp Temp - 30 °C to 60 °C, ONVIF S,G,T	8.00	Ea.	0.00	0.00
290	SITC of 32 Channel Network Video Recorder (NVR), Dual OS design, HDD Hot Swap with RAID support, N+1 hot spare configuration, Support 16CH@2MP, H.265/H.264 Video Compression, HDMI, VGA output, upto 8 SATA interface each with max 10 TB support and 1 eSATA, 16-ch synchronous playback at up to 1080p resolution, Gigabit Ethernet network interfaces, bandwidth 320 mbps, CE FCC, BIS, Operating Temp -10 deg to 50 deg C, USB and serial Interface, RAID supported	1.00	Ea.	0.00	0.00
291	Supply Installation and Testing of 8 TB HDD	4.00	Ea	0.00	0.00
292	Supply, Installation, testing & commisioning of Wire less WiFi Router with below specification Networking Interface : (1) 10/100 Ethernet Port Buttons : Reset Antennas ,Power Method : Passive Power over Ethernet (12-24V) Power Supply : Included 24V, 0.5A PoE Adapter Maximum Power Consumption : 6 W Maximum TX Power : 27 dBm BSSID : Up to Four Per Radio Power Save : Supported Wireless Security : WEP, WPA-PSK, WPA-TKIP,WPA2 AES.	5.00	Ea.	0.00	0.00
293	Supply, installation, testing and commissioning of Providing following type of Modular Type Accessories mounted with pvc / metallic box, single mounting base frame covered with textured / metallic front plate , modules erected with necessary connection. As desired by Engineer In charge.Modem Jack for Computer & Telephone Open RJ-45 CAT III.	120.00	Each	0.00	0.00
294	Supply Installation and Testing of Cat6 I/O for DATA and TELEPHONE - With BASE Plate	300.00	Mtr	0.00	0.00
295	Supplying & erecting approved make LAN cable of following size in existing pipe as per direction [D] CAT - 6e (For LAN, Telephone & Camera).	8500.00	Mtr	0.00	0.00
296	SITC of CAT6 UTP 24AWG PATCH CORD:1M,Plug 30U' Snag less [Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	150.00	Ea.	0.00	0.00
297	SITC of CAT6 UTP 24AWG PATCH CORD:2M,Plug 30U' Snag less [Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	160.00	Ea.	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
298	SITC of Patch Panel Cat 6 UTP Keystone Type- 24 Port-Fully Loaded. Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	7.00	Ea	0.00	0.00
299	Providing & Erecting Netwrok rack with following capacity with Necessary cooling fan,Cable manager,6A PDU,equipment rack with necessary mounting accessories. (A) 1 U	1.00	Ea.	0.00	0.00
300	(B) 6 U	1.00	Ea.	0.00	0.00
Total Amount					0.00
G	Part-7				
301	(C) 12 U	4.00	Ea.	0.00	0.00
302	(D) 16 U	3.00	Ea.	0.00	0.00
303	(E) 22 U	2.00	Ea.	0.00	0.00
304	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge. (4) TV Co-axial Socket outlet	6.00	Each	0.00	0.00
305	Providing & Erecting approved make following size of TV Co-axial flexible cable comprising inner conductor of solid bare copper insulated with Foam PE & Secondary conductor made of poly - Aluminium film bonded Al. Braids @ suitable coverage overall sheathed with black PVC insulation. (e) RG-11	600.00	Each	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
306	FIRE ALARM SYSTEM: Supplying, installation, testing and commissioning of micro processor based intelligent addressable main fire alarm panel having IS or BS (EN 54) (Vds approved) or NFPA 72 (UL/ULC/FM approved) with latest Ammendment with central processing unit with the following loop modules and capable of supporting not less than 240 devices (including detectors) and minimum 120 detectors per loop and loop length up to 2 km, network communication card, minimum 320 character graphics/ LCD display with touch screen or other keypad and minimum 4000 events history log in the non volatile memory (EPROM), power supply unit (230 ± 5% V, 50 hz), 48 hrs back-up with 24 volt sealed maintenance free batteries with automatic charger. The panel shall have facility to connect printer to printout log and facility to have seamless integration with analog/digital voice evacuation system (which is part of the schedule of work under SH: PA System) and shall be complete with all accessories . The panel shall be compatible for IBMS system with open protocol BACnet/ Modbus over IP complete as per specification. (B) 2 Loop Panel	1.00	Ea	0.00	0.00
307	Supplying, installation, testing & commissioning of intelligent analog addressable photothermal detector having IS-11360-1985 or BS 5446 Part I-1977 & Part VII –1985 (VdS approved) or NFPA72 (UL/ULC/FM approved) with Latest ammendment complete with mounting base complete as required.	62.00	Ea	0.00	0.00
308	Supplying, installation, testing & commissioning of intelligent addressable thermal detector with rate of rise cum fixed tempreature thermistor having IS-2175 - 1988 or BS-5445 (EN 54) Part 5 –1977(VdS approved) or NFPA72 (UL/ULC/FM approved) complete with base as required.	3.00	Ea	0.00	0.00
309	Supplying, installation, testing & commissioning of Response Indicator.	31.00	Ea	0.00	0.00
310	Supplying, installation, testing & commissioning of addressable manual call point having IS or BS (EN 54) (Vds approved) or NFPA 72 (UL/ULC/FM approved) with Latest Amendment complete as required.	2.00	Ea	0.00	0.00
311	SITC of Analogue addressable loop powered Base Sounder, variable sound output 50 ~ 98 dB(A) (±2 dB(A)) output at 1 metre, 51 user-selectable tones (all tones EN54-3 compatible), Auto shutdown feature prevents noise-pollution, Approved by LPCB & VdS	2.00	Ea	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
312	Supply and Laying of 2 Core X 1.5 sqmm FRLS armoured copper Cable (Makefinolex /polycab / RR kabel / Avocab	2500.00	Rmt	0.00	0.00
313	PA SYSTEM: Supplying and drawing of cable Fire Retardant PVC insulated copper conductor cable in the existing surface / recessed steel conduit of following pairs, cores and size including connections and interconnections etc. as required. (B)Speaker cable Two pair, 2-core, 1.5 sqmm	1000.00	Rmt	0.00	0.00
314	Supply, installation, testing & Commissioning of 55 inch UHD LED 4K Smart TV with all mounting accessories, remote, Power unit complete. Min 2 USB Port, 2 HDMI Port, VGA Port, Ethernet Port etc. with updated OS. 2023 Latest Model, Make : Sony, Samsung, LG, Vu	2.00	Ea.	0.00	0.00
315	Supply, Installation, Testing and Comissioning of 86" Smart Interactive 4K display 7H hardness toughen anti glared glass In-built Android 8.0, RAM 3 GB, 16 GB ROM with 32 GB SD card) 10 Points Touch in Android and 20 points Touch in Windows Smart Object recognition and responsive multi-touch Multiple Inputs for connectivity 15W x 2 Speakers Inbuilt Screen Sharing Software Slimmer Frame Customize GUI Broadcasting upto 200 Devices Display Management (Including Five year free maintenance with guarantee)	1.00	Ea.	0.00	0.00
316	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (b) 25 mm	4200.00	Mtr.	0.00	0.00
317	Pop-Up Box: The SITC of a Table Mount Retractable Lid Modular Multi-Connection Solution should include a 4-module customizable configuration with a mix-and-match system and slide-and-lock mechanism. It must feature an HDMI Passthrough Port, USB Type-B Port, two Universal Power Sockets, two LAN Ports, ensuring functionality and durability. Make: Kramer - T-IN4-REC2(B)+MP-U(B)(x2)+MD-H+B/AF(B)+MD-2RJ45(B) or Equivalent. Location/Area: Conference.	2.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
318	Switcher: SITC of 4K@60Hz 4:4:4 HDMI Switcher with 4 HDMI inputs, 1 HDMI output, and de-embedded analog audio output. Supports 2K & 4K, 17.82Gbps data rate, HDCP 2.2, HDR10, deep color, CEC, Dolby TrueHD, DTS-HD, and 3D (HDMI 2.0). Features automatic switching, multi-channel audio (32 channels), Maestro Room Control, RS-232, Ethernet, remote contact closure ports, input selection buttons, DIP switches, and mini USB for firmware upgrades. Certified for RoHS, WEEE, and CE compliance. Make: Kramer - VS-411XS or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
319	Disply Mounting Bracket: SITC of Disply Mounting Bracket - Standard including Hardware & Accessories etc. complete as per drawing.. Location/Area: Conference.	1.00	Nos	0.00	0.00
320	Equipment Rack: SITC of Equipment Rack of Rittal (Model Rittal-9U) make or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
321	POE Network Switch: SITC of Cisco switch - Cisco-SG350X-24 make or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
322	SITC of 35 Feet High-Performance Active HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color, featuring 24K gold-plated pins and lockable connectors. The cable is 28 AWG, UL Listed, and meets CL3/FT4 electrical safety standards. It is RoHS 2011/65/EU compliant, ensuring environmental safety and reliability. Make: Kramer - CA-HM-35 or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
323	SITC of 25 Feet High-Performance Active HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color, featuring 24K gold-plated pins and lockable connectors. The cable is 28 AWG, UL Listed, and meets CL3/FT4 electrical safety standards. It is RoHS 2011/65/EU compliant, ensuring environmental safety and reliability. Make: Kramer - CA-HM-25 or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
324	SITC of 15 Feet High-Performance HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color with 24K gold-plated pins and lockable connectors. The cable is 28 AWG, triple shielded for maximum EMI protection, with a flammability rating of CL3/FT4 for safety. It complies with RoHS 2011/65/EU standards. Make: Kramer - C-HM/HM-15 or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
325	SITC of 6 Feet High-Performance HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color with 24K gold-plated pins and lockable connectors. The cable is 28 AWG, triple shielded for maximum EMI protection, with a flammability rating of CL3/FT4 for safety. It complies with RoHS 2011/65/EU standards. Make: Kramer - C-HM/HM-6 or Equivalent. Location/Area: Conference.	3.00	Nos	0.00	0.00
326	Supply, Installation, Testing and Commissioning of 15 Feet High-performance Universal Serial BUS Cable with amplification chipset that supports signals with Data rate upto 5 GBPS or More. Should have Type A male and Type A Fe-male Connectors both the sides.Should have CM-c(ETL) Rated.Should Buffers Incoming & Outgoing Signal. Make: Kramer - CA-USB3/AAE-15 or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
327	supply, Installation, Testing and Commissioning of 15 Feet High-performance Universal Serial BUS Cable with amplification chipset that supports signals with Data rate upto 480Mbps. Should have Type A male and Type A Fe-male Connectors both the sidesShould have CM-c(ETL) Rated.Should Buffers Incoming & Outgoing Signal. Make: Kramer - CA-UAM/UAF-15 or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
328	SITC of 6 feet USB 3.0 Type-A Male to Type-A Male cable supports speeds up to 4.8Gbps, featuring nickel connector plating for durability and foil/overall braid for EMI/RFI protection. It's RoHS compliant. Make: Kramer - C-USB3/AA-6 or Equivalent. Location/Area: Conference.	1.00	Nos	0.00	0.00
329	SITC of a Cat 6a cable includes 4 shielded twisted pairs of 23AWG solid annealed copper conductors, with an LSHF outer jacket and tinned copper drain wire. Operating from -20°C to +60°C, it complies with EIA/TIA 568A, ISO/IEC 11801, IEC 60332 1, and IEC 61034 standards. Additionally, it's halogen-free, RoHS compliant, with optional fire reaction classification Dca-s2,d1,a1 (or B2ca-s1,d1,a1), and recommended by HDBaseT Make: Kramer - BC-UNIKET/LSHF or Equivalent. Location/Area: Conference.	300.00	Nos	0.00	0.00
330	Pop-Up Box: The SITC of a Table Mount Retractable Lid Modular Multi-Connection Solution should include a 4-module customizable configuration with a mix-and-match system and slide-and-lock mechanism. It must feature an HDMI Passthrough Port, USB Type-B Port, two Universal Power Sockets, two LAN Ports, ensuring functionality and durability. Make: Kramer - T-IN4-REC2(B)+MP-U(B)(x 2)+ MD-H+B/AF(B)+ MD-2RJ45(B) or Equivalent Location/Area: Meeting room	1.00	Nos	0.00	0.00
331	Supply, Installation, Testing and Commissioning of High-Performance HDMI Cable supporting 4K@60Hz (4:2:0) and Deep Color with 24K gold-plated pins and lockable connectors. The cable is 28 AWG, triple shielded for maximum EMI protection, with a flammability rating of CL3/FT4 for safety. It complies with RoHS 2011/65/EU standards. Make: Kramer - C-HM/HM-25 or Equivalent. Location/Area: Meeting room	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
332	SITC of High-Performance HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color with 24K gold-plated pins and lockable connectors. The cable is 28 AWG, triple shielded for maximum EMI protection, with a flammability rating of CL3/FT4 for safety. It complies with RoHS 2011/65/EU standards. Make: Kramer - C-HM/HM-6 or Equivalent. Location/Area: Meeting room	2.00	Nos	0.00	0.00
333	Supply, Installation, Testing and Commissioning of 6 feet USB 2.0 Type-A Male to Type-B Male Cable includes a high-speed USB 2.0 cable supporting a maximum data rate of 480Mbps. It features Nickel-plated connectors with foil & overall braid shielding for maximum EMI/RFI protection and ensures compliance with RoHS standards. Make: Kramer - C-USB/AB-6 or Equivalent. Location/Area: Meeting room	1.00	Nos	0.00	0.00
334	Smart Interactive 4K display: Supply, Installation, Testing and Commissioning of 75" Smart Interactive 4K display 7H hardness toughen anti glared glass In-built Android 8.0, RAM 3 GB, 16 GB ROM with 32 GB SD card 10 Points Touch in Android and 20 points Touch in Windows Smart Object recognition and responsive multi-touch Multiple Inputs for connectivity 15W x 2 Speakers Inbuilt Screen Sharing Software Slimmer Frame Customize GUI Broadcasting upto 200 Devices Display Management (Including Five year free maintenance with guarantee) Location/Area : Training room	1.00	Nos	0.00	0.00
335	PTZ Camera: The SITC of a 4K voice-tracking PTZ camera includes 12x optical zoom, 16x digital zoom, 4K 30fps video, and an 8.42MP CMOS sensor with low-light 2D/3D DNR. It supports multiple camera modes, including Presenter Tracking, Auto Framing, Smart Gallery, Speaker Tracking, Multi-Stream, and Manual. The camera features USB 3.0, supports resolutions up to 4Kp30, and offers a $\pm 170^\circ$ pan and $\pm 90^\circ$ tilt with adjustable speeds. It includes H/V flip, an IR remote control, and three built-in microphones with a 180° pickup angle. The device is certified for Microsoft teams, CE, FCC, RoHS, and REACH compliance. Make: Kramer - KAC-CAM-70 or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
336	Wireless Presentation and Collaboration Solution: Device with Airplay, Miracast Technology. 6 user can present simultaneously on single display mode and upto 12 user in dual display mode. 1X HDMI Input for Hardwiring Input, 1X HDMI Output, 1X Display Port OUT, 1x Mic IN and 1x Line Out Ports, 3x USB 3.0 and 2x USB 2.0 Ports, additionally have 128GB SSD for Storage, 8 GB RAM with Windows Platform. Login using conventional Wi-Fi or LAN connections Powerful security features: user authentication, 1024-bit encryption, dynamic room code Supports Windows laptops and MAC, as well as iOS and Android mobile operating systems High quality video streaming, supports 4K@60 (using the VIA app Multimedia feature connect & collaborate Third Party VC Install Support, Should have Via versa feature to access professional grade camera wirelessly. Make: Kramer - VIA Campus2 Plus or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
337	USB Switcher: SITC of a 3x1 4K60 USB-C/HDMI Switcher with DP Alt Mode and PD 3.0 USB-C port for versatile connectivity and power delivery. It includes two HDMI ports, supports 18Gbps bandwidth, resolutions up to 4K@60Hz (4:4:4), HDCP 2.3, Deep Color, 3D, HDR (HDMI 2.0b), and an HDMI Loop port. It offers flexible power options, including PoE and USB-C charging up to 60W, and USB device charging up to 2A. It features a USB 3.1 Host port (USB-C), two USB 3.1 Host ports (USB-B), and four USB 3.1 Device ports (USB-A), supporting USB 3.1 data rates up to 10Gbps and compliance with USB 3.2 GEN 2, 2.0, and 1.1 standards. It includes a built-in Intelligent Control Gateway for remote IP-driven control via CEC, RS-232, IR, or I/O, and complies with CE, UL, RoHS, and WEEE standards. Make: Kramer - SWT3-31-HU or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
338	Pop-Up Box: Supply, Installation, Testing and Commissioning of wall plate of size 8.60cm x 0.25cm x 8.60cm and should have capacity to insert three single module HDMI, lan and USB Type A. Make: Kramer - FRAM-1G/US+W-H(W-HDMI)+WU-AA+W45 or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
339	Wireless Speaker/Mic.: SITC of 6 x 2 Digital Signal Processor with 1 unbalanced (3.5mm) input, 4 mic/line inputs (2 with AEC), and 2 outputs. Features 2x1 HDMI switcher with 2 HDMI inputs, 1 HDMI output, supporting 4K@60Hz (4:4:4) and HDMI audio de-embedding. Supports HDCP 1.4 & 2.2 with per-input HDCP off option. Includes USB port for PC configuration and audio processing, 10 global + 10 mixer snapshot presets, and control via front panel, Ethernet (built-in webpages), and RS-232. CE, ISO 9001, ISO 14001, OHSAS 18001 certified. Make: Kramer - DSP-62-AEC or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
340	Wireless Microphone: SITC of Dual Wireless Microphone System Make: Erthpot - AR-33/21 or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
341	Speaker: SITC of 2-Way Powered Speaker System with 45Hz–20kHz (-10dB) / 50Hz–20kHz (±3dB) frequency response, 6.5" polypropylene woofer with rubber edge & 1" silk dome tweeter, 85dB SPL (1W@1m), max SPL 100dB continuous / 108dB peak. Features volume, bass & treble control knobs, auto power-off with LED indicator, and multiple inputs: 3.5mm mini-jack, balanced terminal block, RCA (L/R). Includes U-shaped rotating mounting brackets for flexible installation. Make: Kramer - Tavor-6-0 or Equivalent Location/Area : Training room	1.00	Pair	0.00	0.00
342	Control Keypad: SITC of Wall-Mounted Control Panel with 6 RGB backlit, touch-sensitive buttons with custom-labeled, removable caps, digital volume control knob, and dual 8-character programmable LCD displays. Features built-in control processor with 1 RS-232, 1 IR, 2 I/O, and 2 relay ports, integrated IR learner, and mini USB for programming. Designed to sync with the primary master room controller and operate within 0°C to 40°C. Supports expansion with additional components to meet specifications. Make: Kramer - RC-63DLN or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
343	Disply Mounting Bracket: SITC of Disply Mounting Bracket - Standard - including Hardware & Accessories etc. complete as per drawing. Location/Area : Training room	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
344	Equipment Rack: SITC of Equipment Rack of Rittal (Model Rittal-9U) make or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
345	POE Network Switch: SITC of Cisco switch - Cisco-SG350X-24 make or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
346	Camera Bracket: SITC of Ceiling Mount Camera mounting Bracket - Standard - including Hardware & Accessories etc. complete as per drawing. Location/Area : Training room	1.00	Nos	0.00	0.00
347	SITC of 25 Feet High-Performance Active HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color, featuring 24K gold-plated pins and lockable connectors. The cable is 28 AWG, UL Listed, and meets CL3/FT4 electrical safety standards. It is RoHS 2011/65/EU compliant, ensuring environmental safety and reliability. Make: Kramer - CA-HM-25 or Equivalent Location/Area : Training room	2.00	Nos	0.00	0.00
348	SITC of High-Performance HDMI Cable supporting 4K@60Hz (4:4:4) and Deep Color with 24K gold-plated pins and lockable connectors. The cable is 28 AWG, triple shielded for maximum EMI protection, with a flammability rating of CL3/FT4 for safety. It complies with RoHS 2011/65/EU standards. Make: Kramer - C-HM/HM-6 or Equivalent Location/Area : Training room	3.00	Nos	0.00	0.00
349	Supply, Installation, Testing and Commissioning of 35 Feet High-performance Universal Serial BUS Cable with amplification chipset that supports signals with Data rate upto 5 GBPS or More. Should have Type A male and Type A Fe-male Connectors both the sides.Should have CM-c(ETL) Rated.Should have Buffers Incoming & Outgoing Signal. Make: Kramer - CA-USB3/AAE-35 or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
350	supply, Installation, Testing and Commissioning of 25 Feet High-performance Universal Serial BUS Cable with amplification chipset that supports signals with Data rate upto 480Mbps. Should have Type A male and Type A Fe-male Connectors both the sidesShould have CM-c(ETL) Rated.Should Buffers Incoming & Outgoing Signal. Make: Kramer - CA-UAM/UAF-25 or Equivalent Location/Area : Training room	2.00	Nos	0.00	0.00
Total Amount					0.00
H	Part-8				
351	SITC of 6 feet USB 3.0 Type-A Male to Type-B Male cable supports speeds up to 4.8Gbps, featuring nickel connector plating for durability and foil/overall braid for EMI/RFI protection. It's RoHS compliant. Make: Kramer - C-USB3/AB-6 or Equivalent Location/Area : Training room	3.00	Nos	0.00	0.00
352	SITC of 6 feet USB 2.0 Type-A Male to Type-A Male Cable includes a high-speed USB 2.0 cable supporting a maximum data rate of 480Mbps. It features Nickel-plated connectors with foil & overall braid shielding for maximum EMI/RFI protection and ensures compliance with RoHS standards. Make: Kramer - C-USB/AA-6 or Equivalent Location/Area : Training room	1.00	Nos	0.00	0.00
353	The SITC of the high-quality twisted pair speaker cable includes a 16 AWG (26/30) bare copper conductor, PVC insulation material, and a rugged, flexible PVC jacket with sequential markings every meter. It has a temperature rating of 75°C and is certified with UL: CM and RoHS 2011/65/EU compliant. Make: Kramer - BC-2S or Equivalent Location/Area : Training room	300.00	Lot	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
354	SITC of high-quality shielded pair audio/control cable supports balanced mono or unbalanced stereo mic or line level audio signals. It features stranded 20AWG tinned copper conductors and a rugged, flexible jacket with sequential markings. The conductor size is 2x20AWG with a diameter of 0.916mm. Insulation diameter is 1.8±0.09mm, and it utilizes AL-foil/mylar screening for effective shielding. Certified with UL: CM and RoHS 2011/65/EU compliant Make: Kramer - BC-1T or Equivalent Location/Area : Training room	300.00	Lot	0.00	0.00
355	HVAC (Air Conditioning work) SYSTEM : SUPPLY & LIFTING, SHIFTING, INSTALLATION, TESTING, COMMISSIONING OF MAKE VARIABLE REFRIGERANT FLOW SYSTEM.OF VARIABLE REFRIGERANT FLOW SYSTEM. Supply & Installation of Variable Refrigerant Volume system with eco friendly R-410a refrigerant Outdoor units comprising of Hermetically sealed Digital scroll / Invertor Scroll Compressors. Cooling Outdoor Units: 40.0 HP	1.00	No	0.00	0.00
356	Cooling Outdoor Units: 12.0 HP	1.00	No	0.00	0.00
357	Cooling Outdoor Units: 5.0 HP	1.00	No	0.00	0.00
358	1Way Type Cassette Unit: 1.5TR	1.00	Nos.	0.00	0.00
359	1Way Type Cassette Unit: 1.0TR	8.00	Nos.	0.00	0.00
360	4Way Type Cassette Unit: 1.5TR	1.00	Nos.	0.00	0.00
361	4Way Type Cassette Unit: 2.0TR	1.00	Nos.	0.00	0.00
362	4Way Type Cassette Unit: 2.5TR	1.00	Nos.	0.00	0.00
363	4Way Type Cassette Unit: 3.0TR	7.00	Nos.	0.00	0.00
364	4Way Type Cassette Unit: 4.0TR	2.00	Nos.	0.00	0.00
365	NON VRF 4Way Type Cassette Unit: 4.0TR	1.00	Nos.	0.00	0.00
366	Remote control: Cordless	22.00	Nos.	0.00	0.00
367	All refrigerant Joints	20.00	Nos.	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
368	Supply & Installation of the following components of VRV system: All refrigerant piping between indoor & outdoor units. Refrigerant pipes should be insulated with Nitrile Rubber Insulation. For VRF System	305.00	Rmt.	0.00	0.00
369	All refrigerant piping between indoor & outdoor units. Refrigerant pipes should be insulated with Nitrile Rubber Insulation. For Non VRF System	60.00	Rmt.	0.00	0.00
370	Supply & Installation of the following components of VRV system: Control cables with pvc conduit between indoor and outdoor unit.	360.00	Rmt.	0.00	0.00
371	Supply & Installation of the following components of VRV system: PVC Drain piping for the units with Insulation.	200.00	Rmt.	0.00	0.00
372	Supply & Installation of the following components of VRV system: Testing & Commissioning charges along with topping-up of refrigerant.	1.00	Lot.	0.00	0.00
373	Supply & Installation of the following components of VRV system: MS Stand For ODU	4.00	Nos.	0.00	0.00
374	Supply & Installation of the following components of VRV system: Cable tray for open are copper pipe	60.00	Rmt.	0.00	0.00
375	Supply & Installation of the following components of VRV system: Power Cable From MCB to Outdoor Unit	60.00	Rmt.	0.00	0.00
376	Supply & Installation of the following components of VRV system: MCB With Weather Protection Box for Outdoor Unit	4.00	Nos.	0.00	0.00
377	Supply & Installation of the following components of VRV system: Power Cable From MCB to Indoor Unit	200.00	Rmt.	0.00	0.00
378	Supply & Installation of the following components of VRV system: MCB for indoor Unit	22.00	Nos.	0.00	0.00
379	Labour charges for Shifting of Existing furniture or any type of work like shifting, remove and Reinstallation/ fixing item as per specified location as per direction by EIC/Architect. etc. complete.	75.00	Man Day	0.00	0.00
	Total Amount				0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
I	Part-9 (Rate Only Item)				
380	Single Leaf Flush Door finish with veneer: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 4 mm thick veneer with matt finish monocoat polish as approved, wooden frame with matt finish monocoat polish, Hardware fittings like door closer, Door handle ,Mortise lock , Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings , fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Basic Rate of teak veneer - 120/Sqft.	Rate Only	Sq.mt	0.00	0.00
381	Providing and fixing 15mm dia Basin spout of as per approved make of selection. Model Equivalent to FLR-CHR-5021M For Handicapped Toilet.	Rate Only	Nos	0.00	0.00
382	Providing and fixing 25 mm thick Marine plywood conforming to IS: 710 / 25 mm thick WPC board as per approved sample by Architect/client on fabrication work . Work complete including all type of fittings , fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client.	Rate Only	Sq.mt	0.00	0.00
383	Double Leaf Glass Door: Supply & Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 & KOPS DF 103 (45mm x 25mm) for Glass door frame Doorframe Dimension – 45mm x 25mm. Finish – SILVER finish / Powder coating as per approved sample by Architect .10mm thk. clear toughened Glass KUBIK Glass Hinge, HAFELE Open Door closer with saddle plate, KUBIK Mortise lock with handle, KUBIK Door stoper etc complete. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights ,, safety measures , necessary frame work,Scaffolding etc complete as per detailed drawings ,specifications & instruction of Client/EIC.	Rate Only	Sq.mt	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
384	Alabaster panelling: " -----Do -----" as per above item specification for complete work . Using 6/8 mm thick Alabaster instead of veneer for panelling work. The rate shall be for all floors, at all heights, all shapes including all costs. Basic rate of Alabaster is Rs. 600/Sqft	Rate Only	Sq.mt	0.00	0.00
385	Cabin table unit: Table top : 1800 x 750x750 mm ht, Side Unit with storage: 1500x 450x750 mm ht, MDU-450x450x650mm. " -----Do-----"-as per above specification for complete work.	Rate Only	Unit	0.00	0.00
386	Workstation : L Shaped : Workstation of size 1870x600x1050 one side and other side 700x600x1050 ht (Ht: 750 mm workstation + 450 mm Glass including brackets). " -----Do-----"as per above specification for complete work .	Rate Only	Nos	0.00	0.00
387	Waiting area Center Table: 750 x 750 x 400 mm Table top: 15 mm thick Artificial stone top. Vertical support: solid woode Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing , all necessary hardware and fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	Rate Only	Nos	0.00	0.00
388	Waiting Lounge area Corner Table: 450 x 450x 400 mm " -----Do-----" as per above specification for complete work.	Rate Only	Nos	0.00	0.00
389	Center Table: size of bigger table-2'6" Dia and smaller table-2' Dia : Project room, workstation Providing & fixing of center table Table top: 15 mm thick Artificial stone top. Vertical support: Metal with powder coating. Work complete including all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	Rate Only	Pair	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
390	<p>Center Table: Size-1'6" Dia (Passage area) Center table : 25 mm thick Solid wooden top with matt finish monocoat polish. Vertical support: solid wooden Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing , all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	Rate Only	Nos	0.00	0.00
391	<p>Waiting Sofa (two Seater): 1500mm (L) x 870 mm (B) x 800 mm (H) made up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density thikness & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish.The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</p>	Rate Only	Nos	0.00	0.00
392	<p>Waiting Lounger chair :The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</p>	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
393	Cabin Sofa (Three seater): 2100 (L) x 870 mm (B) x 800 mm (H) comprising of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt	Rate Only	Nos	0.00	0.00
394	Chair Type-6A (Lunch room Chair) -Model equivalent make -to MonarchMarvella PP chair as per approved sample list. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	Rate Only	Nos	0.00	0.00
395	Seating bench : 2100 x 450 mm (Lunch room) Providing and fixing seating bench with metal leg and with Mattfinish laminated top as approved sample by Architect Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	Rate Only	Nos	0.00	0.00
396	Lunch table : 2100 x 950 mm Providing and fixing seating bench with metal leg and with Matt finish laminated top as approved sample by Architect Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
397	<p>Puffy : Providing & Fixing of Puffy as per approved sample by Architect. Make : Solidwood , Structure : Solidwood , Finish : Fabric Finish (Basic Rate of Fabric is Rs 800 Per Meter) Leg : Wooden Leg Finish : Approved Shade Polish on Wooden Leg Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	Rate Only	Nos	0.00	0.00
398	<p>Supplying and erecting approved make oscillating type bracket fan A.C. 230V. 50cy/s 400/450 mm sweep wall mounted with height adjustment and rotary tilting device complete with guard, flexible Core plug top complete erected with lead wires as directed.</p>	Rate Only	Nos	0.00	0.00
399	<p>Axeon Linear Profile: 40W 8ft, High efficiency long life Linear recessed luminaire with white powder coated finish extruded aluminium housing & continuous option with 56 mm Width & 86 mm Height. Special translucent satin finish colourLED PMMA Diffuser. LED driver duly wired up to terminal block for easy installation and long service. Luminous efficacy not less than 110lm/W. CRI>80, IP20, Ambient temp-0 to 45DegC, Driver efficiency>85%, THD<10%, CCT- 5700K, 50,000 hrs @ L70 life, Powerfactor>0.95, Surge protection-3 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 150-270V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen ≥ 4400lm. Available in continuous as well as standalone configuration. Wipro Model -LM34-501XX-57RMCG1</p>	Rate Only	EA	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
400	<p>MOLLIS X LED DOWNLIGHT SURFACE 18W, High efficient surface mounted LED round downlighter with white powder coated, pressure die cast aluminium housing. High transmittivity PS diffuser provides soft light UGR<19. CRI>80,IP20,Ambient temp-0 to 45DegC, CCT - 4000/5700K, 50,000 hrs @ L70 life.Driver efficiency>85%, THD<10%, Powerfactor>0.95, Surge protection-2.5 kV, Multistage Isolated Constant Current-Constant Voltage operated driver with range 100-265V AC and Safety Extra Low Voltage Safe level<60V DC as per IEC standard. Luminaire lumen ≥ 1800 lm. (100 lm/W), Wipro Model No.LD06-221-XX-57SMG1</p>	Rate Only	EA	0.00	0.00
401	<p>ELATEE 2X2 SURFACE: Integral, SMD 2x2 LED, IP 20, 36W LED Surface mounted drop down fixture with System efficacy of more than 100lm/W and system lumen output 3600lm. Luminaire shall have satin finished translucence (HET) diffuser for Uniform illumination and wider light distribution. LM 80-08 compliant LEDs from reputed makes such as Nichia / Cree / Bridgelux / Lumileds should be provided. LEDs used in the product shall comply with EN 62471 for Photo-biological safety and certificate for the same from manufacturer shall be provided. Luminaire shall use SMD type LED. The LED shall be compliant with LM80-08 standard with L70 life of 50000 Hrs tested at maximum current (Complete LM 80 test report for LED should be submitted for 10000 hrs of testing). The LEDs used should be with CCT of 5700 K and CRI of Minimum 80. LED Driver shall be Multistage, Isolated type, APFC, Constant Current topology driver with proper heat sink for heat dissipation suitable to operate in input voltage range of 150V to 270V (nominal rated voltage – 240V) with 3KV internal surge protection, Power factor greater than 0.95 and total harmonic distortion (THD) of less than 10% should be integral to the luminaire. Complying to SELV < 60V DC standards. Compliance to Indian Standards of IS10322 Part 5 / Sect 1:1967; 16105 : 2012; IS 16106 : 2012; IS 15885 (Part2/Sec13) : 2012; IS 16108 : 2012 Wipro Model No. CRCO10S038HP57G1L1.</p>	Rate Only	EA	0.00	0.00
402	<p>Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, conforming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 16 way SS Double door for horizontal single phase outgoing</p>	Rate Only	Ea	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
403	Providing & erecting weather proof, dust & vermin proof, floor mounted front operated indoor type cubical panel board necessary IP-42 and above protection as per approval from engineer incharge made from 14 SWG thick CRC M.S. sheet for outer body & doors, 16 SWG thick CRC M.S.sheet for internal partitions with necessary accesories , supporting angles/ flats channel including cutting, bending, drilling, welding, riveting with internal partitions & cable alley as per requirements & instruction of engineer-in-charge with erection of supplied switch gears, BUSBARS, suitable size of inter connecting PVC copper wire / copper-aluminium strips, rubber grommets, rib, bakelite control fuses/MCB for measuring instruments, earth bus & earth bolts, foundation flange - bolts-base Plates, sufficient nos. of hinged doors, handles with locking arrangement and rubber gasket,heavy duty end terminal connection,danger notice board,necessary ventilation,earthing strip complete. The Panel shall be painted with epoxy powder coating. (The rates excludes the cost of switchgears, bus bars, inter connecting mains & Copper Aluminium strips, meters, Fuses etc. The dimension shall be measured excluding base beams) The panel shall be supplied with following approved manufacturers with following size.(B) The standard companies switch gear shall be used and only manufacturers at CPRI approved factory. (ii) with 550 mm. Depth	Rate Only	Sq.Mtr	0.00	0.00
404	Supplying and erecting triple pole & neutral 440V/ 500V panel mounting Aluminium Busbars with four equal Nos. of bus having current density not more than 0.8 Amp. / sq.mm (Rated current / cross section area) duly wrapped with colour insulating tape for phase sequence of following current carrying capacity, erected with necessary bus bar supports /insulators, main cable socket to each busbar,erected in existing cubical panel with necessary connections.(D) Suitable for 400 Amp. Capacity	Rate Only	Rn.Mtr	0.00	0.00
405	Providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 50 KA and above at 415 V having Normal current rating 400A. with variable Thermal & magnetic release suitable to work on A.C.supply 50 c/s. With all internal connections, spreader tinned copper & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only Cat III	Rate Only	Ea	0.00	0.00
406	Supplying and erecting approved make Single Phase 20-32A MCB with Outdoor Type Enclosure with mounting accessories.	Rate Only	Ea.	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
407	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (H) 3 1/2 core 185 Sq. mm (95 Sq. mm 1/2 core)	Rate Only	Rmt	0.00	0.00
408	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (B) 3 1/2 core 35 Sq. mm (16 Sq. mm 1/2 core)	Rate Only	Rmt	0.00	0.00
409	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cables. (B) 4 core 16 Sq. mm	Rate Only	Rmt	0.00	0.00
410	Providing and, fixing heavy duty flange type brass double compression type cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (G) 3 & 1/2 core 185 Sq. mm	Rate Only	EA	0.00	0.00
411	Providing and, fixing heavy duty flange type brass double compression type cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (B) 3 & 1/2 core 35/50 Sq. mm	Rate Only	EA	0.00	0.00
412	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (I) 185 Sq.mm.	Rate Only	Ea	0.00	0.00
413	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (D) 35/50 Sq.mm.	Rate Only	Ea	0.00	0.00
414	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (C) 16 Sq.mm.	Rate Only	Ea	0.00	0.00
415	Providing and erecting Annealed bare Copper wire 8 to 16 SWG.	Rate Only	KG	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
416	Supplying and erecting approved make online Un-interruptible Power Supply system comprising flat cum-boost charger with IGBT base rectifier & Inverter & sealed maintenance free SMF batteries. The charger having operating capacity for input 160-270V AC & inverter having output 230V,50 Hz Ac with 0.8 load power factor with battery, over/under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following power backup.with MS painted batteries stand, 10% Overload capacity for momentary load. (J) 20 KVA 3 - phase with 1Hr Backup	Rate Only	Ea.	0.00	0.00
417	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories,Junction Box, Joints as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Make : MK & Legrand. 100mm x 38mm x 1.6mm (1 compartment)	Rate Only	Mtr	0.00	0.00
418	225mm x 38mm x 1.6mm (2 Compartment)	Rate Only	Mtr	0.00	0.00
419	300mm x 38mm x 1.6mm (3 compartment)	Rate Only	Mtr	0.00	0.00
420	Supplying under floor pregalvanised corrosion proof rectangular sheet steel Floor Junction Box with provision of Metallic Lid for Carpet or Flooring Tile of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Make : MK & Legrand. 150mm x 150mm x 55-70mm deep	Rate Only	Ea	0.00	0.00
421	250mm x 250mm x 55-70mm deep	Rate Only	Ea	0.00	0.00
422	350mm x 350mm x 55-70mm deep	Rate Only	Ea	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
423	SITC of 24 x 10/100/1000BASE-T PoE ports 4 x Gigabit RJ45/SFP Combo ports Advanced L2 switching and security features L2+ Static Routing Optional "standard mode" or "surveillance mode" management user interface 193 W PoE budget [Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	Rate Only	Ea	0.00	0.00
424	GENERAL PA SYSTEM: Supplying & erecting Amplifier having following specification: Power Output :250W (RMS) (300W Max.) inputs : 6 Misc. & 2 Aux. frequency Response :50-1500HZ I3db Tone Controls :Cut & Boost type LED Meter :5 LED Arrays The amplifier suitable to operate 240V A.C.& 24volt D.C. (Battery) with automatic changeover from AC to Battery operation, duly protected by wrong Battery Polarity connections. [[Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	Rate Only	7-3-3.	0.00	0.00
425	Supplying & erecting four channel Echo Mixer Pre-amplifier with following specification. (i) Suitable to operate on 240V.A.C. & 12 V D.C. Battery supply (ii) B.B.D. Delay system ECHO facility on all inputs through ECHO volume, Repeat & Delay system. (iii) Peak LED for setting optimum distortion free input levels (iv) Two outputs, variable for line & fixed for recording (v)Compatible with Audio Mixing consoles. [[Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	Rate Only	Ea.	0.00	0.00
426	Supplying & erecting recess wall mounting speaker with 6W rated input power 3.3 K. Ohms / 3W impedance, 100 - 10000 Hz frequency response with 6 inch dia. cone type 8 ohms speakers duly fitted in ABS plastic cabinet of colour match with wall or ceiling of following size. [[Approved by Competent Authority i.e. not Below the rank of Executive Engineer] (a)Round Shaped, 230mm dia. Speaker	Rate Only	Ea.	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
427	Supplying, erecting & testing Approved make Microphone for announcement, speech & general P.A. application with frequency response of 150 - 10000 Hz having sensitivity 2mv/Pa, & impedance 600 Ohms supplied with quick detachable holder, 6 mtr twin core cable & PCIM / MCIF connector. [[Approved by Competent Authority i.e. not Below the rank of Executive Engineer]	Rate Only	Ea.	0.00	0.00
428	Supply, installation, testing & Commissioning of 65 inch UHD 4K LED Smart TV with all mounting accessories, remote, Power unit complete. Min 2 USB Port, 2 HDMI Port, VGA Port, Ethernet Port etc. with updated OS. 2023 Latest Model, Make : Sony, Samsung, LG, Vu	Rate Only	Ea.	0.00	0.00
429	Supply, Installation, Testing and Comissioning of 75" Smart Interactive 4K display 7H hardness toughen anti glared glass In-built Android 8.0, RAM 3 GB, 16 GB ROM with 32 GB SD card) 10 Points Touch in Android and 20 points Touch in Windows Smart Object recognition and responsive multi-touch Multiple Inputs for connectivity 15W x 2 Speakers Inbuilt Screen Sharing Software Slimmer Frame Customize GUI Broadcasting upto 200 Devices Display Management (Including Five year free maintenance with guarantee)	Rate Only	Ea.	0.00	0.00
	Total Amount				0.00
J	Part-10 (Rate Only Item)				
430	Supply, Installation, Testing and Commissioning of USB enrollement biometric reader, supports ISO 19794-2, ANSI 378 template format, support RAW, BMP, WSQ, ISO 19794-4 image template, support live finger detection, IP65 certified, operating temperature -10 to +50 degree celcius, with certificate CE, FCC, KC, ROHS, USB-IF, WEEE, WHQL, FBI IPV/FIPS 201 FBI mobile ID FAP10	Rate Only	Ea	0.00	0.00
431	Providing & erecting approved make Card Reader having following features. [A] Wiegand / RS232 Interface (B) Power supply from COSEC Door controller or through Separate Adaptor (C) Compatible with any COSEC Door controllers (D) 4 LEDs (Status, Alarm, Allowed and Denied) and Buzzer (E) Tamper Detection	Rate Only	Ea	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
432	Providing & erecting approved make Panel Controller for Multiple Door Controllers having following feature (A) Controls up to 16 Door Conditioners (B) Ethernet RS485, USB,Aux Input and Aux Output Port (C) 10000 Users Capacity and 100000 Events Storage (D) 32-bit processor, 32 MB RAM and 32MB Flash (E) Compact and Elegant Design	Rate Only	Ea	0.00	0.00
433	Providing & erecting approved make Application Software Platform for 500 Users having following features (A) With 100 Users (B) Expandable up to 500 Users with COSEC USER100 (C) Supports up to 16 Door Controllers (D) Basic Access Control, Basic Time Attendance and Enrolment Management (E) Compatible with all COSEC Hardware (F) Add Other COSEC software Modules on requirement.	Rate Only	Ea	0.00	0.00
434	Smart Interactive 4K display: Display with OPS: Supply, Installation, Testing and Comissioning of 75" Smart Interactive 4K display 7H hardness toughen anti glared glass In-built Android 8.0, RAM 3 GB, 16 GB ROM with 32 GB SD card) 10 Points Touch in Android and 20 points Touch in Windows Smart Object recognition and responsive multi-touch Multiple Inputs for connectivity 15W x 2 Speakers Inbuilt Screen Sharing Software Slimmer Frame Customize GUI Broadcasting uto 200 Devices Display Management (Including Five year free maintenance with guarantee). Location/Area: Conference.	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
435	PTZ Camera: SITC of PTZ Camera with 12X optical & 16X digital zoom, 2D & 3D DNR, USB 3.0 & RS232 interfaces, and 1080P to 240P video support. Features a 1/2.7-inch sensor or better, f3.5mm42.3mm, F1.8F2.8 lens or better, ±170° pan, -30° to +30° tilt, and high-speed pan/tilt control. Certified for CE, FCC and compliant with RoHS, WEEE. Make: Kramer - K-CamHD or Equivalent. Location/Area: Conference.	Rate Only	Nos	0.00	0.00
436	Wireless Presentation and Collaboration Solution: Device with Airplay, Miracast Technology. 6 user can present simultaneously on single display mode and upto 12 user in dual display mode. 1X HDMI Input for Hardwiring Input, 1X HDMI Output, 1X Display Port OUT, 1x Mic IN and 1x Line Out Ports, 3x USB 3.0 and 2x USB 2.0 Ports, additionally have 128GB SSD for Storage, 8 GB RAM with Windows Platform. Login using conventional Wi-Fi or LAN connections Powerful security features: user authentication, 1024-bit encryption, dynamic room code Supports Windows laptops and MAC, as well as iOS and Android mobile operating systems High quality video streaming, supports 4K@60 (using the VIA app Multimedia feature connect & collaborate Third Party VC Install Support, Should have Via versa feature to access professional grade camera wirelessly. Make: Kramer - VIA CAMPUS2 Plus or Equivalent. Location/Area: Conference.	Rate Only	Nos	0.00	0.00
437	HDMI Transmitter: SITC of an HDMI to HDBaseT extender supporting bi-directional RS-232 and IR, 18Gbps data rate, up to 40m at 4K@60Hz (4:4:4) and 70m at 4K@30Hz (4:4:4), with HDTV, HDCP 2.2, HDR10, 3D pass-through, Deep Color, x.v.Color™, Lip Sync, Dolby TrueHD, DTS-HD, CEC, and compliance with CE, ISO 9001, ISO 14001, and OHSAS 18001 standards. Make: Kramer - TP-583T or Equivalent. Location/Area: Conference.	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
438	<p>HDMI Receiver: SITC of an HDBaseT to HDMI receiver supporting bi-directional RS-232 and IR, 18Gbps data rate, up to 40m at 4K@60Hz (4:4:4) and 70m at 4K@30Hz (4:4:4), with HDTV, HDCP 2.2, HDR10, 3D pass-through, Deep Color, x.v.Color™, Lip Sync, Dolby TrueHD, DTS-HD, CEC, and compliance with CE, ISO 9001, ISO 14001, and OHSAS 18001 standards.</p> <p>Make: Kramer - TP-583R or Equivalent.</p> <p>Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00
439	<p>Chairman Unit: Supply,Installation,Testing and Commissioning of Flush Mount Chairman Unit with mute button which mute integrated Mic and override button which prioritizes itself over all other delegate Units. The unit comes with a screw type detachable microphone port to connect gooseneck microphones. Integrated Microphone with variable length of 10 inch and 15 inch . The microphone features a cardioid condenser polar pattern and a frequency response range of 50Hz to 20kHz. With a sensitivity of -20dBV (+/-3dB) at 1kHz, it efficiently converts sound pressure into electrical signals. It can handle a maximum input sound pressure level of 110dB with low distortion (<0.1% THD). The microphone operates on a 24V DC power supply (supplied by the controller) with a power consumption of 0.72W. It connects via an RJ45 network input and boasts a recessed enclosure design for discreet integration. Constructed with a high-quality copper zinc alloy die-cast body, it offers durability. Its detachable screw-type gooseneck microphone enhances flexibility in positioning. Additionally, it features a backlit speak & override button for improved usability, especially in low-light environments.</p> <p>Make: Erthpot - NCS-5CF or Equivalent.</p> <p>Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
440	<p>Deligate Unit: Supply, Installation, Testing and Commissioning of Flush Mount Delegate Unit with mute button which mute integrated Mic. The unit comes with a screw type detachable microphone port to connect gooseneck mic .Integrated Microphone with variable length of 10 inch and 15 inch. The microphone features a cardioid condenser polar pattern and a frequency response range of 50Hz to 20kHz. With a sensitivity of -20dBV (+/-3dB) at 1kHz, it efficiently converts sound pressure into electrical signals. It can handle a maximum input sound pressure level of 110dB with low distortion (<0.1% THD). The microphone operates on a 24V DC power supply (supplied by the controller) with a power consumption of 0.72W. It connects via an RJ45 network input and boasts a recessed enclosure design for discreet integration. Constructed with a high-quality copper zinc alloy die-cast body, it offers durability. Its detachable screw-type gooseneck microphone enhances flexibility in positioning. Additionally, it features a backlit speak & mute button for improved usability, especially in low-light environments.</p> <p>Make: Erthpot - NCS-5DF or Equivalent. Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00
441	<p>Gooseneck Mic.: Supply , Installation , Testing and Commissioning of 16" Gooseneck Mic for NCS Unit . Condenser Mic with Cardioid Polar Pattern with frequency range of 100 Hz to 15KHz . Open Circuit Sensitivity of Mic is -47dB. Maximum SPL of Mic is 105dB at 1 KHz. Signal to noise ratio is 52dB at 1 KHz at 1Pa.</p> <p>Make: Erthpot - NGM-516 or Equivalent. Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
442	<p>Control unit: Supply, Installation, Testing & Commissioning of Conference Controller System, Should have Digital in nature with Dante Audio output and with 4 or more Kinds of Conference Modes Including FIFO Mode, Request Mode, Automatic Mode, Voice activation mode, the central controller should able to Select the No. of speakers and Active 2/3/4 Mics simultaneously, Should support 110 Number of microphones supported via additional power supply unit, supports camera Tracking thru RS-232 & RS-422 Communication Protocols or more, Should have supports 4 or more Video inputs and 1 output port on SDI and HD-SDI video format or better, Should able to connect and control up to 4 cameras simultaneously with in built auto switching between cameras as per microphones connected to them. The Controller should Compatible with any PTZ camera having Visca, Pelco D, and Pelco P Control mode protocols. It should have Dante digital output along with Analog XLR and Phono output complete with standard accessories required Make: Erthpot - NCS-110CU or Equivalent. Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00
443	<p>DSP: System Installation ,Testing and Commissioning of Digital signal processor with min. 04AEC enabled Mic/Line inputs, 04 Line outputs or better , Input channel processing should include Pre amplifier, Signal generator, Expander, Compressor, 10 band Parametric EQ or better, Output Channel processing should include 31 band Graphic equalizer, Delay, Crossover, limiter or better, Other features should include Automatic mixing console, Ducker, Feedback elimination, Noise elimination, echo elimination or better, Should have built-in Bi directional USB for Software based VC as well as for playing digital audio, Should have built in Camera tracking Module, 8 Port Freely Configurable GPIO or better with Analog/Digital dynamic range of 114dB or better, Sampling rate of 48Khz or better, Frequency response of 20Hz – 20Khz or better, per channel phantom power module or better. Should be configurable thru software. Make: Erthpot - KEYER 44 or Equivalent. Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
444	<p>Amplifier: SITC of Class D Amplifier with 240W (70V/100V) or 2x120W (4/8Ω), 2 inputs with individual gain, balanced & unbalanced inputs, EQ, HPF, and auto-standby. Controllable via screw trimmer, RS-232, and Ethernet. Supports 20Hz–20kHz, -80dB SNR, 119dB dynamic range, with overcurrent & overheat protection. CE, ISO 9001, ISO 14001, OHSAS 18001 certified.</p> <p>Make: Kramer - PA-240Z or Equivalent.</p> <p>Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00
445	<p>Speakers: SITC of 2-Way Coaxial Ceiling Speaker with 6.5" woofer, 0.5" tweeter, 8Ω impedance, and 80Hz–20kHz frequency response. Handles 30W RMS, 80W program power with 70V/100V transformer taps & switchable low impedance mode. Offers a 101° coverage angle for wide sound distribution.</p> <p>Make: Kramer - Galil 6-C or Equivalent.</p> <p>Location/Area: Conference.</p>	Rate Only	Pair	0.00	0.00
446	<p>AV Controller: The SITC of a control processor should control one standard space without a physical brain and offer a customizable UI. It must include three USB ports, one LAN port, one HDMI input/output, and feature an Intel® Gemini Lake QC SOC or better, running Linux with 4GB RAM and 32GB eMMC storage. The system should support 4 bidirectional RS-232. Certifications: CE, ISO 9001, ISO 14001, OHSAS 18001.</p> <p>Make: Kramer - KC-Virtual Brain1+FC-24ETH or Equivalent.</p> <p>Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00
447	<p>Touch Panel GUI: SITC of 8-inch LCD Touch Panel Wall & Table Mount PoE Control Touch Panel features an ARM Quad-core Cortex-A53 CPU (up to 1.8GHz, 64-bit), 4GB LPDDR4 RAM, and 32GB eMMC storage, running on the latest Android 11 operating system. It boasts an 8-inch capacitive multi-touch display (1280x720, 16:9), built-in 2x 1W speakers, dual microphones, and a 5MP camera, supporting various audio and video codecs. Connectivity includes Wi-Fi 6, Bluetooth 5.0, and a 10/100/1000 Mbps Ethernet port. The display offers 350cd/m² brightness and a 1000:1 contrast ratio. It supports PoE (802.3af) and optional 12V/2A DC power. Safety standards include CE, FCC, UL, UKCA, while environmental regulations comply with RoHS and WEEE.</p> <p>Make: Kramer - KT-208 or Equivalent.</p> <p>Location/Area: Conference.</p>	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
448	SITC of high-quality shielded pair audio/control cable supports balanced mono or unbalanced stereo mic or line level audio signals. It features stranded 20AWG tinned copper conductors and a rugged, flexible jacket with sequential markings. The conductor size is 2x20AWG with a diameter of 0.916mm. Insulation diameter is 1.8±0.09mm, and it utilizes AL-foil/mylar screening for effective shielding. Certified with UL: CM and RoHS 2011/65/EU compliant Make: Kramer - BC-1T or Equivalent. Location/Area: Conference.	Rate Only	Nos	0.00	0.00
449	The SITC of the high-quality twisted pair speaker cable includes a 16 AWG (26/30) bare copper conductor, PVC insulation material, and a rugged, flexible PVC jacket with sequential markings every meter. It has a temperature rating of 75°C and is certified with UL: CM and RoHS 2011/65/EU compliant. Make: Kramer - BC-2S or Equivalent. Location/Area: Conference.	Rate Only	Nos	0.00	0.00
450	LED Smart TV: Supply, installation, testing & Commissioning of 65 inch UHD 4K LED Smart TV with all mounting accessories, remote, Power unit complete. Min 2 USB Port, 2 HDMI Port, VGA Port, Ethernet Port etc. with updated OS. 2023 Latest Model, Make : Sony, Samsung, LG, Vu Location/Area: Meeting room	Rate Only	Nos	0.00	0.00
451	Wired & Wireless Presentation Solution: Device with Airplay, Miracast Technology. 6 user can present simultaneously on single display mode and upto 12 user in dual display mode. 1X HDMI Input for Hardwiring Input, 1X HDMI Output, 1X Display Port OUT, 1x Mic IN and 1x Line Out Ports, 3x USB 3.0 and 2x USB 2.0 Ports, additionally have 128GB SSD for Storage, 8 GB RAM with Windows Platform. Login using conventional Wi-Fi or LAN connections Powerful security features: user authentication, 1024-bit encryption, dynamic room code Supports Windows laptops and MAC, as well as iOS and Android mobile operating systems High quality video streaming, supports 4K@60 (using the VIA app Multimedia feature connect & collaborate Third Party VC Install Support, Should have Via versa feature to access professional grade camera wirelessly. Make: Kramer - VIA Campus2 Plus or Equivalent Location/Area: Meeting room	Rate Only	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
452	All In One Conference bar: SITC OF compact, all-in-one video and audio communication bar offers a single-cable setup and multiple connection options. It features a 12 MP camera with a 120° viewing angle, 5x digital zoom, and auto-framing for dynamic field of view adjustment. Additionally, it includes six microphones with an 8-meter voice pickup distance, an integrated 8-way speakerphone with automatic noise reduction and gain control. Control is facilitated via a remote control for functions like zoom, camera position selection, and audio volume. Accessories include 1 USB-C cable, remote control, power cord and adapter, lens cover, wall bracket kit, and screws set. Safety and environmental compliance include CE, FCC, RoHS, and WEEE standards Make: Kramer - K-Bar or Equivalent Location/Area: Meeting room	Rate Only	Nos	0.00	0.00
453	supply, Installation, Testing and Commissioning of 25 Feet High-performance Universal Serial BUS Cable with amplification chipset that supports signals with Data rate upto 480Mbps. Should have Type A male and Type A Fe-male Connectors both the sidesShould have CM-c(ETL) Rated.Should Buffers Incoming & Outgoing Signal. Make: Kramer - CA-UAM/UAF-25 or Equivalent. Location/Area: Meeting room	Rate Only	Nos	0.00	0.00
454	Hi-Wall Split Unit: 1.5TR	Rate Only	Nos.	0.00	0.00
455	Hi-Wall Split Unit: 1.0TR	Rate Only	Nos.	0.00	0.00
Total Amount					0.00
K	Part-11 (Buy Back Item)				
456	Part-II: Buyback items:- Note: 1) The client reserves the right for hand over of any buy back items to bidder without assigning any reason thereof. The client reserves the right for any decision. 2) The Qty may vary for any buy back item as per actual site conditions. Metal Warbrode Full Ht. size-1200 X 2100 X 400(W), Location: Record Room	4.00	Nos	0.00	0.00



**ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT
FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.**

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
457	Metal Warbrode 4'ht. size 1050 X 1200 X 400 (W), Location: Record Room	2.00	Nos	0.00	0.00
458	Metal Rack-1800 X 300mm x 2400 Ht, Location: Record Room	90.00	Nos	0.00	0.00
459	Wooden Wardrobe- 1050X600mm, Location: Record Room	4.00	Nos	0.00	0.00
460	Table-1800 X 900mm,side unit- 1500 X 400mm Laminate finish table with side unit , Location: Record Room	1.00	Nos	0.00	0.00
461	1 Seater sofa , Location: Record Room	3.00	Nos	0.00	0.00
462	1 Seater sofa , Location: I Create Room	2.00	Nos	0.00	0.00
463	3 Seater Sofa , Location: I Create Room	1.00	Nos	0.00	0.00
464	Center Table - 1050 x 600 mm : Glass top & laminate finish center table , Location: I Create Room	1.00	Nos	0.00	0.00
465	Reception table-1800X600mm ; 1050mmht. Laminate fnish table , Location: I Create Room	1.00	Nos	0.00	0.00
466	Discussion Table- 900mm Dia Glass top & metal legs , Location: I Create Room	1.00	Nos	0.00	0.00
467	Conference Table- 2400 X 900mm Glass top & laminate finish table , Location: I Create Room	1.00	Nos	0.00	0.00
468	Conference Chairs, Location: I Create Room	7.00	Nos	0.00	0.00
469	Conference Room 3Seater Sofa, Location: I Create Room	1.00	Nos	0.00	0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
470	Conference Room 1Seater Sofa : , Location: I Create Room	2.00	Nos	0.00	0.00
471	Center Table - 1050 x 600 mm Glass top & laminate finish center table , Location: I Create Room	1.00	Nos	0.00	0.00
472	Training hall Chair, Location: I Create Room	28.00	Nos	0.00	0.00
473	Storage-1200 x 400 x 750 mm ht Laminate finish storage , Location: I Create Room	1.00	Nos	0.00	0.00
474	Table-1800 X 900mm,side unit- 1250 X 400mm :Laminate finish table with side unit , Location: I Create Room	1.00	Nos	0.00	0.00
475	Table-1500 X 900mm,side unit- 1250 X 400mm Laminate finish table with side unit , Location: I Create Room	2.00	Nos	0.00	0.00
476	Visitor Chair, Location: I Create Room	11.00	Nos	0.00	0.00
477	Tiled or stone floors , wall tiled / any type of cladding material	1789.00	Sq.mt	0.00	0.00
478	All toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank , Urinal , all type of cock , accessories , basin counter etc. (Male & Female toilet & D toilet)	1.00	Job	0.00	0.00
479	Existing All type of Door , window with frame all hardware's	46.00	Nos	0.00	0.00
480	Existing Glazing with frame work : Elevation facade & Atrium side	104.00	Sq.mt	0.00	0.00
481	Existing Electrical light fixtures , cables , trays , etc	1.00	Job	0.00	0.00
482	Existing fabrication/ Steel structure / S.S. railing etc. work	1500.00	Kg	0.00	0.00
Total Amount					0.00



ALTERATION, MODIFICATION, INTERIOR FURNITURE, ELECTRICAL, FIREFIGHTING, HVAC AND OTHER REFURBISHMENT WORKS AT FIRST FLOOR OF CORPORATE OFFICE BUILDING OF GMDC, VASTRAPUR, AHMEDABAD, GUJARAT.

PRICE BID

Sr. No.	Item Description	QTY	Unit	Rate	Amount
Sr. no.	Summary Sheet				Amount
A	Sub Total : Part - 1				0.00
B	Sub Total : Part - 2				0.00
C	Sub Total : Part - 3				0.00
D	Sub Total : Part - 4				0.00
E	Sub Total : Part - 5				0.00
F	Sub Total : Part - 6				0.00
G	Sub Total : Part - 7				0.00
H	Sub Total : Part - 8				0.00
I	Sub Total : Part - 9 (Rate Only Item)				0.00
J	Sub Total : Part - 10 (Rate Only Item)				0.00
	Total Amount (Rs.)				0.00
K	Sub Total : Part -11 (Less Bay back Amount)			less	0.00
	Grand Total Amount (Rs.)				0.00

GST Extra as per Govt. Norms