

## GUJARAT MINERAL DEVELOPMENT CORPORATION LIMITED

**T-No-08/MNM/CAUSEWAY/2026, Work of Construction of Causeway in mine area at GMDC Lignite Project, Mata No Madh, Tal: Lakhpat, Dist: Kutchh**

### PRICE BID

Sr. No.	Description	Qty	UNIT	RATE	AMOUNT
1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff with all lead and lift.(B) Dense or Hard Soil	377.00	Cmt.		
2	Providing and filling in foundation with ordinary cement concret M100 mix and providing necessary vetical pin headers including formwork vibrating ramming and curing complete.	32.40	Cmt.		
3	Providing and filling in foundation with ordinary cement concret M150 mix and providing necessary vetical pin headers including formwork vibrating ramming and curing complete.	134.50	Cmt.		
4	Providing and casting in situ ordinary cement concret M150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete without V-grooves (Height from 0.0 M to 5.0 M	126.30	Cmt.		
5	Providing and casting in situ ordinary cement concret M100 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete without V-grooves (Height from 0.0 M to 5.0 M	294.90	Cmt.		
6	Supplying and fixing reinforced concrete heavy duty non pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level or slopes) of class NP3 of following internal daimeters.(vii) 1200mm dia.	150.00	Rmt.		
7	Providing and laying W.B.M. of M.C. metal of size 45 mm to 90 mm size including 0.27 Cu.M. Stone screening & 0.08 Cu.M. stone dust as filler including spreading, watering & consolidation by vibratory roller 80KN to 100KN static weight. 100 mm thick compacted	27.00	Cmt.		
8	Proving and laying cement concrete Grade M20 (1-cement :1.5 sand : 3.0 coarse agg. Of 20mm nominal size) for CC road and curring etc. comp. incl. cost of form work. Finishing the cement concrete road by Tri-mix process inclusive of labour charges for trimix vacume dewatering process on cement conc. road by using vacume dewatering pump, surface floater, including chanelling and making grooves & rough finish to surface, providing expansion join, construction joint incl. filling the joint with asphalt filler as per direction by engineer in charge and as per specification.	90.50	Cmt.		
9	Providing TMT Bar FE 550D reinforcement for R.C.C. work including bending, binding and placing in position complete.	2422.00	Kg.		
10	Earth work for embankment with selected soil C.B.R.not less than 6.0 including breaking clods, dressing, with all, lead and lift (excl. watering and consolidation) From borrow area with all lead & lift.	224.00	Cmt.		
11	Rolling & watering and consolidation earthwork using vibratory road roller 8 - 10 tonne capacity (A) Earth work	224.00	Cmt.		

Total